

30 May 2023

Department of Environment, Science and Innovation - Coal Business Centre
PO Box 3028,
Emerald QLD 4720

By email: CRMining@des.qld.gov.au

Attention: Juliana McCosker; Priti Mahajan; Jessica Edgar

FOXLEIGH MINE – INFORMATION REQUEST NOTICE RESPONSE

On 1 September 2023, Foxleigh Management Pty Ltd submitted a PRCP (encompassing both the PRCP – Rehabilitation Planning Part and PRCP – Schedule) for the Foxleigh Coal Mine to the Department of Environment, Science and Innovation (DESI). DESI subsequently issued an Information Request Notice to Foxleigh Management Pty Ltd on 30 October 2023, requiring Foxleigh Management Pty Ltd to provide additional information to address identified potential issues within the submitted PRCP by 30 April 2024. An extension of one month was granted to 30 May 2024.

Attachment 1 provided with this letter documents Foxleigh Management Pty Ltd responses to the DESI Information Request Notice and is submitted together with a revised PRCP – Rehabilitation Planning Part (V2) and PRCP – Schedule (V2), which are intended to replace the originally submitted documents.

Yours sincerely



[Andrew Boyd \(May 30, 2024 10:12 GMT+10\)](#)

Andrew Boyd
Managing Director

environment water quality monitoring data of minimum past 2 years . - Contaminant of concern (CoC) based on the mining process and waste characterisation. - potential sources/pathways of contaminant during the post closure phase (such as surface runoff from rehabilitated areas, flood water etc.) and mitigative measures.	reflects both insitu and laboratory data collected through Environment Monitoring Program over the last four years. The Appendix I section 4.4 provides overview of surface water quality through the monitoring conducted insitu at four upstream control sites and three downstream impact sites, but the period of sampling for Table 6 is not clear. Overall, the PRC plan does not provide baseline water quality monitoring data, contaminants of concern (CoC), and potential pathways of contaminant post closure. The information is important as it helps to determine the water quality limits, suitability of monitoring locations to demonstrate the stability and non-polluting state of the final rehabilitated landform. [The section identifies the relevant waterways and their environmental values. Appendix I section 4.4 provides overview of surface water quality through the monitoring conducted insitu at four upstream control sites and three downstream impact sites, but the period of sampling for Table 6 is not clear.]
Contaminant of Concern (CoC), sources of contaminant of concerns post rehabilitation and the potential pathways onsite that may end up to surface water post closure. The Appendix I section 4.4 provides overview of surface water quality through the monitoring conducted insitu at four upstream control sites and three downstream impact sites, but the period of sampling for Table 6 is not clear. Overall, the PRC plan does not provide baseline water quality monitoring data, contaminants of concern (CoC), and potential pathways of contaminant post closure. The information is important as it helps to determine the water quality limits, suitability of monitoring locations to demonstrate the stability and non-polluting state of the final rehabilitated landform. [The section identifies the relevant waterways and their environmental values. Appendix I section 4.4 provides overview of surface water quality through the monitoring conducted insitu at four upstream control sites and three downstream impact sites, but the period of sampling for Table 6 is not clear.]	environment water quality monitoring data of minimum past 2 years . - Contaminant of concern (CoC) based on the mining process and waste characterisation. - potential sources/pathways of contaminant during the post closure phase (such as surface runoff from rehabilitated areas, flood water etc.) and mitigative measures.
Groundwater Monitoring Vibrating Wire Piezometer (VWP) bores and Alluvial Standpipe Monitoring (ASM) bore. PRCP Section 3.5.1, sub-section, ‘Groundwater Use’ states that the local groundwater monitoring network at Fox comprises of a vibrating wire piezometer (VWP) monitoring network and groundwater monitoring standpipes. The section includes Table 3-39 (later Table 8): Fox VWP Monitoring Network which provides details of vibrating wire piezometer bores, FPVWP01, FPVWP02 and FPVWP03 and FPMB01 (ASM bore). Appendix I on Page 24 explains that historically groundwater pressure monitoring has been conducted by using above mentioned three VWP strings installed in 2014. However, no data from VWP or FPMB01 is provided in Appendix I. The 2016 AGE report, ‘Foxleigh Plains Groundwater Monitoring and Management Plan’ provides water level data for ASM bore (FPMB01) for the period from December 2013 to November 2015. It is not clear why data from the ASM bore is not presented in Appendix I or used in model calibration. This information is considered important as it provides some historical data. Further on Appendix I, Page 25 it is explained that there is significant uncertainty surrounding the data coming from the VWPs and this data has not been relied on to assess either regional or local groundwater levels or vertical fluxes between strata. Page 25 also states that in 2021 there were an additional thirteen new groundwater monitoring standpipes that were installed on site. Overall, it has been observed that there is lack of historical groundwater level data in the submitted groundwater assessment. The PRC plan section 3.1.3 or the Appendix I does not clarify which bores from the VWP network or the newly installed standpipe network form the functioning part of the site groundwater network. This information is important to determine the data reliability and determine that mine activities are non-polluting.	Provide an updated PRC planning part/Appendix I that includes – - Clarification on which bores from Appendix I, Table 8 and 9 form the functioning part of the current groundwater monitoring network. - Justify the inclusion of bores in the groundwater monitoring network based on their capacity to provide a useful dataset for groundwater assessment. Please provide this justification - Analysis of adequacy of current GW monitoring network to monitor impacts of Foxleigh mining operation on environmental values (EVs) of GW.
Clarification of which bores form the functioning part network: Section 1.2.5.3 Groundwater Monitoring Network Planning part, and describes the current monitoring plan. - The Foxleigh Groundwater Monitoring Management Plan included as a new Appendix U. This plan was developed as part of the Rehabilitation Milestones for the current monitoring program in consideration of the GMMP – 23 within the conditions of the EIA. See note below for justification of the inclusion of the GMMP – 23 within the conditions of the EIA. - See note below for justification of the inclusion of the GMMP – 23 within the conditions of the EIA. Justification of the inclusion of bores in the groundwater monitoring network: Appendix U (GMMP-23) provides the reasoning for the inclusion of bores in the groundwater monitoring network, and also provides an explanation for why the bores are included in the ongoing monitoring program. - Analysis of adequacy of current groundwater monitoring network. Appendix E of the GMMP-23 (Appendix U) is a part of the GMMP-23 providing a detailed groundwater monitoring plan. Note: Clarification of the relevance of FPMB01 for model development: - FPMB01 was drilled on 28/11/2013 from ground level and 15.14 metres below ground surface (mbgs), with and gravel pack between 11.9-15.1 mbgs in low permeability alluvium with a falling head test result indicating approx. 9E-09 m/s. Well development was completed and bailed over two days due to the very low recovery rate. Monitoring between 8/12/2013 – 7/2/2014 indicated events exceeding 20 mm (on four occasions) and mbgs (123.47 mAHD) (within the screened section). FPMB01 monitors alluvial groundwater perched on top of the claystone due to its hydraulic disconnection from the Permian aquifer.	Clarification of which bores form the functioning part network: Section 1.2.5.3 Groundwater Monitoring Network Planning part, and describes the current monitoring plan. - The Foxleigh Groundwater Monitoring Management Plan included as a new Appendix U. This plan was developed as part of the Rehabilitation Milestones for the current monitoring program in consideration of the GMMP – 23 within the conditions of the EIA. See note below for justification of the inclusion of the GMMP – 23 within the conditions of the EIA. - See note below for justification of the inclusion of the GMMP – 23 within the conditions of the EIA. Justification of the inclusion of bores in the groundwater monitoring network: Appendix U (GMMP-23) provides the reasoning for the inclusion of bores in the groundwater monitoring network, and also provides an explanation for why the bores are included in the ongoing monitoring program. - Analysis of adequacy of current groundwater monitoring network. Appendix E of the GMMP-23 (Appendix U) is a part of the GMMP-23 providing a detailed groundwater monitoring plan. Note: Clarification of the relevance of FPMB01 for model development: - FPMB01 was drilled on 28/11/2013 from ground level and 15.14 metres below ground surface (mbgs), with and gravel pack between 11.9-15.1 mbgs in low permeability alluvium with a falling head test result indicating approx. 9E-09 m/s. Well development was completed and bailed over two days due to the very low recovery rate. Monitoring between 8/12/2013 – 7/2/2014 indicated events exceeding 20 mm (on four occasions) and mbgs (123.47 mAHD) (within the screened section). FPMB01 monitors alluvial groundwater perched on top of the claystone due to its hydraulic disconnection from the Permian aquifer.

any discussion as to how mining has impacted groundwater levels and quality based on the groundwater monitoring data. To understand the impact over the period, water level plots (hydrographs) and quality time series plots of the contaminants of concerns are required for all monitoring bores to demonstrate how groundwater levels and quality has changed over time.	water. b. Hydrographs and quality time series plots of the contaminant of concern for all monitoring bores. Note: The hydrographs and quality time series plots should be accompanied by discussion as to whether any changes in the groundwater level or quality are the result of climatic conditions, mining, or other localised water use.	b. The new Appendix T- Groundwater Monitoring Results collates the results of groundwater monitoring collected over the last 3 years. Note 1: Section 1.2.5.5 of the PRCP has been updated to groundwater levels, in addition to water level data collected over the last 3 years. Note 2: The RFI questions relating to the Groundwater Functionality Report from the initial submission of the PRCP have been replaced by the Appendix I has replaced the original report.	Post-Mine Landforms identifies the monitoring parameters that are monitored as part of the Rehabilitation RA's. Section 7.4.6: Groundwater Monitoring Results collates the results of groundwater monitoring collected over the last 3 years. b. The new Appendix T- Groundwater Monitoring Results collates the results of groundwater monitoring collected over the last 3 years. Note 1: Section 1.2.5.5 of the PRCP has been updated to groundwater levels, in addition to water level data collected over the last 3 years. Note 2: The RFI questions relating to the Groundwater Functionality Report from the initial submission of the PRCP have been replaced by the Appendix I has replaced the original report.
This information is necessary to understand the contaminants of concern generated by the mining activities and to demonstrate risks posed to environmental values have been identified and will be mitigated during rehabilitation to ensure the land achieves a stable condition.	Groundwater data in Table 7 Appendix I, section 6.1.1 states that Table 7: Regional groundwater monitoring bores lists the regional groundwater monitoring bores utilised to prepare a regional groundwater level plan. Many of the columns in Table 7 has been left blank and need to be populated with the specified information. A full data set is required to confirm that the regional groundwater level plan is based on comprehensive data and that the consultations drawn in Appendix I regarding the stability and non-polluting nature of the final landforms are reliable.	5.1 Provide an updated Appendix I that includes – a. Bore specific onsite background groundwater quality and level data for standpipes P1-P12 since 2021.	a. Table 7 is populated in the new Annex A – Groundwater Monitoring Results. b. Refer to the new Annex C – Supplementary Figures figure: Groundwater level contours for 1999 (Figure Appendix I is a water table map based on data points mining condition and model steady state starting conditions presented in Figure 11, data available to plot pre-Foxleigh are sparse and single-formation – no multi-level formation. Furthermore, in the absence of any contradictory evidence, sparse historical data available, the assumption has been made that the groundwater pressures in underlying formation are hence hydraulic head in each formation/unit equals the groundwater level. Note 1: Section 1.2.5.5 of the PRCP has been updated to groundwater levels, in addition to water level data collected over the last 3 years. Note 2: The RFI questions relating to the Groundwater Functionality Report from the initial submission of the PRCP have been replaced by the Appendix I has replaced the original report.
Groundwater quality Appendix I, section 6.1.2 has Table 8: Foxleigh VWP network and Table 9: Foxleigh groundwater monitoring network which provides information on the location, elevation, total depth of the monitoring bores and the targeted formation by each bore but does not provide information on the quality of groundwater monitored at these bores. Appendix I, section 6.3 provides a summary of the monitoring of field water quality conducted at thirteen bores installed in 2021 (refer Table 12: 2021 GWMB field water quality summary). Overall Appendix I or PRC plan does not provide a groundwater quality monitoring data log that can help determining a trend in groundwater quality.	Provide updated Appendix I that includes following – a. Updated Table 21 in addition to location co-ordinates showing depth, target geological unit, water level, elevation and	5.1 Provide an updated Appendix I that includes – a. Bore specific onsite background groundwater quality and level data for standpipes P1-P12 since 2021.	a. A new Appendix T- Groundwater Monitoring Results collates the results of groundwater monitoring collected over the last 3 years. Note: The faulted synclinal geological structure present in the area limits any potential for off-site groundwater level or quality therefore ongoing monitoring of P1 – 12 bores has been made within the document (Appendix U). The purpose of the PRCP Groundwater Model (as per Appendix I). a. A replacement Appendix I has been attached to the PRCP - Table A1 as the replacement Table 21. b. Annex C - Figure A1 is the map showing the location of the bores.
Model Calibration Appendix I Table 21: Calibration target sites provides location coordinates for the 17 bores used in the steady state calibration and very limited data has been provided in the report for these bores except for P1, P12 and P2. This information is required to provide a robust model for the steady state pre-mining modelling.			

section 11.4.1 is not provided in Table 29.

section 11.4.4.1 is not provided in Table 29.

Appendix O, section 3.5 states that maximum groundwater inflow rate to each void as shown in Table 3-4 is used as the input for the GoldSim model. It appears that 'Maximum Flow Rate values' in Table 3.4 are based on Appendix I Table 29. A comparison is shown in below table supporting the assumption that GoldSim model in Appendix O likely to be based on maximum inflow rate to each void considering the bottom depth level rather than a Flux (range of inflow over time).

Appendix I: GW Modelling report Table 29		Appendix O: Final Void Hydrology Report Table 3.4	
Pit Name	Bottom of pit (mAHD)	Maximum Flow Rate (L/s)	Maximum Flow rate (L/s)
Far South	70.50	0.16	0.16
WC	119.54	3.60	3.6
Eagles Nest	--	10.56	10.56
Carlo Creek	56.94	0.48	0.48
One Tree West + Pipeline	-13.78	5.50	5.5
Foxleigh Plains North	40.46	18.02	18.02

It is noted that the void water levels will change over time considering the direct rainfall, surface runoff input to the void and evaporation. Accordingly, the groundwater inflow rate may change over time corresponding to the fluctuating void water levels and that change/flux needs to be considered for void hydrology modelling. Hence it is important to understand if the modelling is based on a groundwater flux or maximum groundwater inflow rate as this will determine the predictions of long-term water levels in the voids

b. If not, provide updated modelling results based on the groundwater flux consideration.

any modelling with lower flows would have produced the presented outcomes are “worst-case”. Refer to n and justification.

Note: The word ‘flux’ is used in Appendix I to mean a continuous, may be unchanging in magnitude in relation to consideration) (Merriam-Webster definition), whilst the continuous state of change. It is inferred that DES is interpreted meaning. In the sense used in Appendix I, the relevant data Appendix O (WRM) Table 3.4 aligns correctly with Appendix the initial model iteration fluxes (using the meaning of the used to derive an interim void lake level which is used in the modelling to compute void lake level-dependent groundwater fluxes in App I).

Temporal influences on groundwater fluxes / inflow rates indicated in IP7.2 above, the groundwater inflow maxima by WRM as per WRM Table 3.4, comprised inputs to the balance modelling to determine final pit lake level. Subsequent and groundwater flow modelling used lesser groundwater hydraulic gradients.

5Y

research study	developed using the bores marked in green only. More explanation of how this map was developed is required. This information provides confidence in what is actually being presented with these contours and how that supports the overall assessment. In addition to Figure 12 the following map/figures are required – The steady state groundwater level elevation contours providing the starting point for the transient calibration. Predicted groundwater level elevation contours for all major model layers (including those representing targeted coal seams) for the end of mining period and post closure period. The above contours are important to understand the relationship between the predicted long term groundwater levels in all units that could be connected to the voids and the predicted long term water levels in the voids.	• The steady state groundwater level elevation contours providing the starting point for the transient calibration. • Predicted groundwater level elevation contours for all major model layers (including those representing targeted coal seams) for the end of mining period and post closure period.	• These sources have included information obtained from monitoring bores (Table 7 – Annex A - Appendix I), historical standpipe (Table 8 – Annex A - Appendix I) installed’ monitoring network (Table 9 – Annex A - Appendix I) • When compiling these spatially and temporally correlated hydrogeologically discrete (fault/thrust-bounded aquifer) units, we have considered the probable contemporary mining activities and the plausible reflecting interaction with surface drainage network structure. • Contours are based on Annex A - Appendix I Tables P1, P2 and P12. Tabular data presented in Appendix I. b. Additional figures have been compiled. Refer to the Figures – Appendix I for maps prepared illustrating: • Groundwater level contours for 1999 (Figure A1) • Groundwater level contours for end of mining (Figure A2) • Groundwater drawdown in various model layers (Figure A3) • Groundwater level contours for post closure (Figure A13)
	Predicted long term water levels. Section 4 of the Appendix O provides a lowest regional groundwater level measured at all voids as 122.5 m AHD. This level is used to compare predicted long term water levels in all pits to determine if the void will be a sink or source. However, there is no justification provided for the use of 122.5 m AHD to represent long term groundwater levels, in all geologic units in contact with all voids. Additional groundwater elevation contours (refer to item 8) are required to demonstrate a realistic long term groundwater level elevation adjacent all voids and provide confidence in the long-term groundwater levels used to determine sink or source predictions.	9.1 Provide updated Appendix O that includes – a. Justification for the use of 122.5m AHD to represent long term groundwater levels, in all geologic units. b. The above justification needs to be in consideration with the additional groundwater elevation contours that are requested in above item 8.	a. WRM has not based the model outcomes on the 122.5m AHD level. The 122.5m AHD has been used as a reference point in the Appendix O groundwater balance model uses inflows of surface water and groundwater together with evaporation and rainfall etc, to calculate the mining groundwater level of 122.5m AHD was selected. The modelled groundwater levels at the time of writing of the model is considered conservative in nature as it represents a lake could be considered a source. level deemed most appropriate is drawn Figure A1 – Annex C – Appendix I contours have been used to determine mining groundwater contour for each of the voids, and the results from Appendix O and Appendix I, to show the voids being a groundwater sink is still valid when compared to the groundwater levels at the location of each void, rather than a more conservative groundwater level. b. In the absence of pre-mining groundwater monitoring data, the modelled heads have been used to infer the pre-mining groundwater levels – Annex C – Appendix I). This assumed pre-mining groundwater levels influence predicted mining impacts on the modelled groundwater levels conservative trigger for the determination of void sink

	<table><tr><th rowspan="2">Void</th><th rowspan="2">bottom of pit/ floor level (m AHD)</th><th colspan="2">Discrepancy</th><th colspan="2">long term median void Water Level/ modelled average (m AHD)</th></tr><tr><th>App. I, Table 29</th><th>App. O, Table 4.1</th><th>App. I, Table 30</th><th>App. O, Table 4.1</th></tr><tr><td>Eagle Nest</td><td>Not provided</td><td>-104</td><td>?</td><td>98.3</td><td>41.5</td></tr><tr><td>Foxleigh Plains</td><td>40.46</td><td>-130</td><td>170.46 m</td><td>48.3</td><td>71.6</td></tr><tr><td>One Tree West (includes pipeline)</td><td>-13.78</td><td>-29</td><td>13 m</td><td>71.7</td><td>47.7</td></tr><tr><td>Pipeline</td><td>above</td><td>-43</td><td>NA</td><td></td><td>67.4</td></tr><tr><td>WC</td><td>119.54</td><td>-15</td><td>134.54 m</td><td>42.6</td><td>42.8</td></tr><tr><td>Far</td><td>70.5</td><td>70</td><td>Nil</td><td>81.6</td><td>81.3</td></tr><tr><td>South Carlo</td><td>56.94</td><td>86</td><td>29.06 m</td><td>44.4</td><td>105.6</td></tr></table>	Void	bottom of pit/ floor level (m AHD)	Discrepancy		long term median void Water Level/ modelled average (m AHD)		App. I, Table 29	App. O, Table 4.1	App. I, Table 30	App. O, Table 4.1	Eagle Nest	Not provided	-104	?	98.3	41.5	Foxleigh Plains	40.46	-130	170.46 m	48.3	71.6	One Tree West (includes pipeline)	-13.78	-29	13 m	71.7	47.7	Pipeline	above	-43	NA		67.4	WC	119.54	-15	134.54 m	42.6	42.8	Far	70.5	70	Nil	81.6	81.3	South Carlo	56.94	86	29.06 m	44.4	105.6		b. Updated Table 4.1 and accordingly updated prediction of residual void behaviour.
Void	bottom of pit/ floor level (m AHD)			Discrepancy		long term median void Water Level/ modelled average (m AHD)																																																	
		App. I, Table 29	App. O, Table 4.1	App. I, Table 30	App. O, Table 4.1																																																		
Eagle Nest	Not provided	-104	?	98.3	41.5																																																		
Foxleigh Plains	40.46	-130	170.46 m	48.3	71.6																																																		
One Tree West (includes pipeline)	-13.78	-29	13 m	71.7	47.7																																																		
Pipeline	above	-43	NA		67.4																																																		
WC	119.54	-15	134.54 m	42.6	42.8																																																		
Far	70.5	70	Nil	81.6	81.3																																																		
South Carlo	56.94	86	29.06 m	44.4	105.6																																																		
	Void salinity Table 3.3: Adopted salinity concentration from section 3.4 indicates that a salinity of 55,000 mg/L has been adopted for the water balance model configuration. The 55,000 mg/L salinity concentration appears to be significantly higher than the figures presented in section 6.3 of the Appendix I: GW Modelling Report. Appendix I, section 6.3 states average electrical conductivity (EC) of 55,000 µS/cm for alluvial formation and same section, Table 12: 2021 GWMB field water quality summary shows a range of EC of 32,073 to 42,765 µS/cm for the various formations. Based on a conversion from EC to TDS of about 0.67 the range of figures in Appendix I, Table 12 convert to 21490 mg/L to 28,650 mg/L and the 55,000 µS/cm quoted in the text converts to 36,850 mg/L. All of these figures are considerably lower than the 55,000 mg/L used in Appendix O. Further clarification required to justify use of 55,000 mg/L salinity in Appendix O for water balance model configuration.	11.1 Provide updated Appendix O and PRC plan that includes – a. Justification for use of 55,000 mg/L salinity to represent groundwater in the water balance model configuration when the data in Appendix I shows lower salinity range.																																																					
“Commentary on discrepancies in modelled void” re-modelling is not considered necessary to address the original Appendix I Table 29 and Table 30 has been included in Table A4 and A5 -Annex B – Appendix I , with inclusion of the new data.	b. Table 4.1 – Appendix O has been updated in the new model in the provided pit shell data for Eagles Nest as there was a discrepancy that went very deep. Eagles Nest should be -65m RL as per the information of the maximum depth in the pit shell data. The new modelled peak long-term water level.	a. Appendix O (WRM) has been amended to fix the error in salinity units. Salinity used was meant to be EC of 55,000 to 36,850 mg/L. See the amended Table 3.3 - Appendix salinity – Appendix O presents the recalculated salinity.																																																					

The PRC plan indicates that the proposed grazing PMLU will be based on land class 4 and is partially consistent with EA Appendix 2 completion criteria which states land class 4 as an optional completion criteria for ‘Areas where agricultural land use applies’. The Agricultural Land Evaluation Queensland Guideline (Second edition) classify land class 4 as a land with severe limitations and unable to successfully sustain a use of land. Hence the proposed land class 4 may not be supportive of proposed cattle grazing PMLU. Appendix K: Geochemical characterisation of waste material in section 4.2.2 have identified the soil types found within the Foxleigh mining lease as Chromosols (45%), Sodosols(20%), Arenosols (20%), Anthroposols (12%) and vertosols (1%). Further the section states, ‘only Arenosols are considered good growth medium able to support both grasses and trees, with the remaining soil types supportive only of native grass/vegetation.’ It is unclear – a) why an alternative land outcome such as Native Ecosystem as stated in the EA Appendix 2 has not been considered; and b) how proposed unsuitable land class will sustainably support the proposedPMLU of grazing.	will achieve following: - Land suitability class of ≤3 as per Agricultural Land Evaluation in Queensland (Second Edition) guideline and; - The rehabilitation planning practices for grazing as a post-mining land use¹ as published by the Queensland Mine Rehabilitation Commissioner Or An alternative PMLU such as Native Ecosystem. This should include a rehabilitation methodology and SMART criteria (Example: BioCondition Framework*) for the Native Ecosystem PMLU. 1. https://www.qmrc.qld.gov.au/research/post-mining-land-uses/grazing	documents related to rehabilitation and closure outcomes regulatory authority gives continued approval for implementation LODs describe a pre-approved land outcome at Fox of low suitability. - EA-Appendix 2 -Rehabilitation Requirements - Rehabilitation Management Plan (submitted to the regulatory authority) - Environmental Management Plan drafted in 28/04/2001 - Environmental Management Overview Strategy 2003. - EIS Assessment Report (dated 12/04/2001) Section 1.3 and Section 3.1.1 of the amended PRCP reproduce these LODs, as they pertain to the pre-approved land outcome. The “<i>Rehabilitated mined land suitability for beef cattle grazing Technical Paper 1”</i> (Short, 2023) notes that: <i>Commercial grazing opportunities (i.e for profit) rehabilitation can be grazed in conjunction with seasons (never in drought), for relatively short periods of time</i> The technical paper further notes that it will require careful grazing, and the stocking rate for the area, to maintain land and water degradation. As per agreements with the previous landholders of Fox, is to support a grazing platform grazed in association with eg. for “low-intensity” grazing for short periods of time as in keeping with the reference above (Short, 2023).	Since FoxMan commenced operations at Fox, ongoing consultation with stakeholders who hold a genuine interest in the land and operational performance, and outcomes, as outlined in the PRCP. These have included, neighbouring landholders, the Commonwealth government agencies, and LGA Council members. Section 2 of the amended PRCP has been updated to better reflect stakeholder engagement post-2013. Section 2.2.2: Stakeholder Engagement PRCP process includes a summary of the topics addressed in the pre-approved PMLUs, where applicable, are consistent with the local area and are strongly supported by the community consultation to date on these PMLUs has resulted in: - No queries or issues with the PMLUs have been received from other members of the local community to date; - No queries or issues with the PMLU have been received from stakeholders. Section 3.3 and Section 4.2 of the amended PRCP have been updated to which each PMLU or NUMA for land identified in the PRCP consistent with any strategies or plans for the land of a local government or the Commonwealth.
Community Consultation In terms of assessing the proposed PMLU’s (grazing, watercourse and native ecosystem corridor) against the outcomes of community consultation, section 3 states, ‘Achievement of the identified PMLU’s (grazing, watercourse and native ecosystem corridor) is in line with consultation completed to date.’ The “Fox Consolidated Consultation Register” presented in Table 3-30 contains limited information on the outcomes of community consultation in regard to developing post mining land uses for the site, particularly post 2013. Therefore, it is not clear whether recent changes to the PMLU’s (approved via major amendment in August 2023) for site are consistent with the prior consultation. This information is important to understand the extent of proposed PMLU and NUMA aligning with the community expectations and required as per section 126C(1)(d) of the EP Act	14.1 Provide an updated PRC planning part that shows that the proposed PMLU and NUMA are consistent with the outcome of community consultation.	15.1 Provide an updated PRC planning part that– a. State the extent to which each post-mining land use for land identified in the PRCP schedule for the plan is consistent with any	
Strategies or plans for the land of a local government, the State or the Commonwealth Section 3.3 does not give consideration to whether the proposed PMLU is consistent with any strategies or plans for the land of a local government, the State or the Commonwealth as required per s126(1)(d) of the EP Act.			

	The PMLU for the undisturbed area has not been defined in the spatial files and PRC plan (e.g. final site design map). (Refer to the red bordered area in below image which shows approximate extent of undisturbed Foxleigh mining lease area). Retained Infrastructure PRC plan section 3.1.9 states that an area totalling 745.518ha of infrastructure is to be retained in accordance with the landholder statements. The landholder statements are supportive of retaining access roads and tracks post mining. The PRC plan nor the spatial data provide a map showing the exact location and details of the infrastructure to be retained . The PRCP schedule RM1: Infrastructure decommissioning and removal, milestone criteria states that, ‘sumps or dams that do not form part of final landform as sediment control structures dewatered and contaminated silt removed, this raises a question if there are in dams/sumps/water structures that likely to be retained post mine and if so what the associated PMLU is. The PRC plan also does not clarify if any rehabilitation steps apply to infrastructure to be retained to ensure it is safe, not cause environmental harm and stable for the purpose post closure.	17.1 Provide updated PRC plan that includes – - Clarification on which infrastructures to be retained onsite post mine and associated PMLU. - A map showing the exact location of infrastructure to be retained. - Any rehabilitation steps that are required to ensure retained infrastructure is safe and stable for post mine use. - A spatial file showing a separate polygon for infrastructure to be retained and associated PMLU.	- To clarify which infrastructure will be retained onsite amended PRCP outlines the PMLU of retained infrastructure agreements for the retention of infrastructure with landholders. These agreements cover the retention of - Bitumen based roads which require little maintenance - or - Roads made of benign alluvial materials which are also non-polluting and stable. Pre-existing infrastructure on easements that cross the post-mining: - the Barwon Park–Middlemount Road easement - BMA water pipeline easement; - A map showing the location of infrastructure to be retained amended PRCP – Figure 3 4 Retained Infrastructure - The new RM12 Achievement of post-mining land use Infrastructure PMLU) has been created (see RFI 38) (as outlined in Table 5-25: Rehabilitation Milestones PRCP). In addition, monitoring methods, contingency records and documentation required to demonstrate amended PRCP Appendix V: Demonstration of Milestones - The new Retained Infrastructure PMLU and the new been included in the updated schedule and spatial files NB. there is NOT 745.518ha of retained infrastructure included infrastructure areas for rehabilitation. Areas of land area of the PRCP that are being allocated to Landholder up to 176.38 ha. This includes: 86 ha of Foxleigh retained infrastructure (ie retained landholder agreements. 63.76 ha has been calculated to lie within the 24.45 ha has been calculated to lie on “undisturbed 16.65 ha apportioned to the BMA pipeline within
--	--	--	--

available on site as per the 2022 Topsoil inventory. The PRC plan (at page 126) states topsoil application depth ranging from 150-200mm and a rehabilitation trial indicating 150mm topsoil depth supporting decent vegetation. The PRC plan does not clarify the following – • Since the site has surplus topsoil, why topsoil application depth of up to or more than 200mm is not proposed at-least for areas prone to erosion risk. • How does the dispersive nature of soil support the proposed minimum topsoil application rate of 150mm for a self-sustaining, stable PMLU • Has a target range of growth medium nutrients identified to support a self-sustaining PMLU. The above information required for determining SMART rehabilitation criteria for surface preparation rehabilitation milestone in PRCP schedule. The above information required for determining SMART rehabilitation criteria for surface preparation rehabilitation milestone in PRCP schedule.	b. Justification how the above-mentioned domain specific topsoil application rate supports achieving the self-sustaining and stable PMLU. c. Target range of growth medium nutrients in accordance with the relevant PMLU (Cattle grazing/Native Ecosystem).	b. Rehabilitation trials at Fox (<i>2021 Rehabilitation Trials</i>) Mine, 2022), and rehabilitation Inspections (<i>Historical Regen</i> 2021) have indicated that a minimum of 15t/ha of topsoil is required for successful revegetation. However, where a topsoil surplus has been achieved, it can be directed to rehabilitation areas RA6, RA7, and RA8 as they hold the greater propensity to erosion. c. The milestones outlined in Section 5.10.1 of the amended AQP and suitability assessment to be completed by a AQP within a rehabilitated landform. The assessment requires exchangeable sodium potential, electrical conductivity and quality is suitable to achieve the relevant PMLU. For all PMLUs within RM7 – Achievement of surface water quality has been included within the amended PRCP requiring soil sampling undertaken at 12 months and 5 years after the completion of the rehabilitation (where required) requiring the following parameters to be met: • Plant Available Water Capacity (PAWC); 30 - 40 mm • Bicarbonate P (at 0 -10cm depth); 4 - <8 mg/L • Electrical Conductivity (1:5 dilution) (in the form of dS/m . • Soil pH as measured at any part of the root zone • Exchangeable Sodium Percentage (ESP%) (a measure of salinity) • Slope <10%, ESP <14% • Slope >10%, ESP <6%
Amelioration Section 3.5.8 (page 126) states that topsoil will be ameliorated with gypsum due to the dispersive nature of topsoils available on site to provide greater stability of soil organic matter. The section proposes a gypsum application rate of 15t/ha and fertiliser application rate of 0.2t/ha based on soil sampling results in accordance with Appendix K. The PRC plan nor Appendix K clarify how the proposed gypsum and fertiliser application rate supports the topsoil to achieve the required nutrient level supporting grazing or native ecosystem PMLU. The plan does not specify targets for total nitrogen, phosphate, organic matter and ESP. Further information is required to ensure the appropriateness of the milestone criteria.	19.1 Provide updated PRC plan that includes – a. Explanation on how the proposed gypsum and fertiliser application rate was derived. b. Topsoil amelioration based on nutrient targets mainly for Total Nitrogen, Phosphate, Organic matter and ESP.	a. Section 5.3.4.4 of the amended PRCP has been updated to propose topsoil to best determine the specific application rate of gypsum fertiliser. The previously stated rate of 15 T/ha of gypsum fertiliser maximum rate of application, as it is recognised that some soils may require such a high rate. The fertiliser rate of 0.2 T/ha rate to allow for extra application for poorer fertility milestones outlined in Section 5.10.1, these applications have been included. These practices are in keeping with rehabilitation practices and will ensure topsoil in suitably rehabilitated landforms. b. Rehabilitation management practices and milestones require an AQP to determine amelioration requirements placement on a rehabilitated landform. Furthermore, additional topsoil added to RM7 to reach PMLU.

	Indian Couch <i>Bothriochloa pertusa</i> or <i>Seca Stylosanthes</i> spp.	combination of species cognisant of grazing best management (2022). Alternative palatable native grass species will be considered if successful may be added to the standard seed mix.
It is noted that Appendix K, section 4.2.2 states that ‘the site comprises of mostly Chromosols (45%), Sodosols (20%), Arenosols (20%), Anthroposols (12%) and Vertosols (1%). Out of above only Arenosols are considered good growth medium able to support both grasses and trees, rest all supportive only of native grass/vegetation’. Considering the soil characteristics, it is not clear why the proposed seed mix includes predominantly non-native and invasive grass species. This information is important to determine the self-sustaining and non-polluting nature of the final landform.	21.1 Provide updated PRC plan/Appendix H that includes: - Clarification why the catchment and surface area in Table 1.1 of the Appendix H differs to the EA Appendix 4: Approved Residual void surface area. - If required update the flood modelling according to residual void area stated in the EA Appendix 4.	- The flood study (Appendix H) catchment area of each it includes land surrounding the void that drains into of the voids (shown in the original Appendix H Table and therefore the actual NUMA hectares is smaller than “void water body surface area” is a smaller area inside flooded void. Figure 5-18 in the amended PRCP illustrates area and NUMA area. None of these stated areas for and the NUMA summary statistics were provided in a reference to indicate which voids were included in the table has been amended to include the areas stated from the ‘Final void hydrology report’ dated 08/04/2022 Environment Pty Ltd). - The flood modelling was not required to be updated surface areas. However, the flood modelling was red protection landforms in place. An amended Appendix Planning Part.
It is not clear if the discrepancy is a typo error or has a rational behind it. Clarification required as the change in NUMA area may impact the flood modelling outcomes. Stream Gauging Data Section 3.3.2 of the Appendix H states, ‘<i>All the stream gauging station rating tables do not extrapolate high enough to provide flow estimates for the January 2013 event.</i>’ In this case following is not clear – - If the absence of ability to extrapolate high enough flow data affects the reliability of the model output. - Can other “minor” rainfall events be used to demonstrate the predictive reliability of the model. For example, can less intense rainfall and baseflow be used in the calibration process? - Can this predicted flow be statistically compared with measured data as a means of supporting the model outcomes such as those presented in Figure 3.4.	22.1 Provide updated PRC plan/Appendix H that includes: Flood assessment outcomes despite limitations of the input data	No change to the modelling inputs to the flood study not considered that it would make an alterable difference. However, Section 3.2.5: Stream Gauging Data, and 3.3.2: Stream Gauging Data H has been updated to further clarify and justify the absence or ability to extrapolate the rating curves to common limitation of most flood model calibrations this into account. The January 2013 flow event in Roost density or records, of which was a key focus of the model design hydrology results from the calibrated model v peak flow estimation techniques which reaffirms model design event simulation and the assessment of flood

	Understand the impact of flooding in the event of diversion failure is required to understand long term site and landform stability specially the rehabilitated TSF area considering its proximity to the creek.		diversions fail.	creek diversion or flood protection landforms. Therefore, flooding does not pose a stability risk. Section 5.3.2 - Appendix H has been updated to include criteria of flood velocity, stream power, and the diversions took all of these things into account scenarios, the flood extent is well beyond the creek diversions. iii. Section 5.3.3 of Appendix H has been added to ensure the flood protection landforms to ensure the event of a flood	
	Flood flow velocity modelling Section 6 of the Appendix H states that flood flow velocity modelling indicates rates of >3.5 m/s for 0.1% AEP and PMF. Erosion potential at these velocities (with vegetation cover) are considered possible, but the magnitude of erosion and its impact on final landform stability and maintenance needs more detailed information. Flow rates of >3 m/s have the potential to erode particularly when flowing water is in contact with erodible soil materials. It is noted that PRC plan section 3.5.4 and Appendix K states the soil quality as dispersive, hence prone for erosion. It is also noted that proposed PMLU for the site predominantly is cattle grazing, and the section 6 of the Appendix H suggests overall risk of erosion from flooding in absence of long-term well-established vegetation.	24.1 Provide updated PRC plan/Appendix H that:	a. Demonstrates the final landform stability under extreme rainfall events and considering the relevant PMLU/Native Ecosystem.	Section 5.3.2.4: Flood Risk Profile of the amended PRC plan has been updated to include relevant Milestone criteria that address this risk. With the addition of flow concentration such as drains, landform depression peak flow velocities are greater than 2 m/s. The milestoned protection for the final landform under extreme rain scenario. Note: Flow velocities >3.5m/s in the 0.1% AEP and PMF erosion creek channels and occur in the pre-mining scenario. Velocity landforms are predicted to be much lower as shown by the H.	
	Water Diversions The PRC plan section 3.5.7 provides information on water management including diversions. Page 120 the PRC plan states that, ‘Management of the Cockatoo Creek diversion will incorporate subsoil amelioration with gypsum’. It is not clear if the section means to refer to subsoil or topsoil. The addition of gypsum suggest dispersive soil material which is supported by the findings in Appendix K: Geochemical Characterisation of Waste Assessment in regards to soil characteristics. As the addition of gypsum is a temporary solution, its application to soil that is used to construct permanent diversions raises a question on the long-term stability of the diversion. It is noted that the PRC plan does not identify the soil types used in constructing the diversions. The Appendix R: EIS statement assessment report (page 1252 of the PRCP) states, ‘there are ongoing issues at the existing operation related to the highly erodible nature of the on-site materials used in existing flood and surface water diversion levees and cracking zones at the top of pit walls.’ Information on soil materials used in constructing the permanent diversions is required to understand long term erodibility and diversion stability.	25.1 Provide updated PRC plan that includes:	a) Clarification on use of gypsum for soil that is used in the construction of diversion and the role it plays in the long-term stability of the diversion. b) Mitigative measures/alternative resources considered for diversion construction that can enhance the long-term stability of the diversion. c) Details on construction materials used in permanent diversions and how the construction material supports the longterm stability of the diversion post closure.	a. The paragraph relating to gypsum, topsoil and the creek included without adequate context, and has thus been removed. Excess of subsoil removed during construction of the diversion this material was stockpiled, and it was noted that if this would likely need gypsum amelioration. As this paragraph management it has been deleted. b. On review of the rest of section “Creek Diversions and Requirements” in the original “Section 3.5.7: Water Management” reflect the required content of this section in the PRCP tracked changes. • The monitoring programme of the water diversions Section 7: Monitoring, under 7.4.7 PMLU Watercourse Diversions; Flood mapping results have been updated to reflect moved to be in the Section 5.3.3: Flooding under Watercourse Diversions; • Guidelines followed for construction of diversions have been incorporated into Section 3.1.2: Watercourse Diversions; • The subsoil (stockpile) amelioration with gypsum relevant. c. The diversion is inspected annually, and any areas identified incorporated into planned remediation works. This information DESI in the form of the Annual Regulated Structures Condition G8-G12 of the EA.	

The above information is important to determine SMART rehabilitation milestone criteria for Surface preparation.

- assessment, as was a cover level that is required to be implemented of these practices aligns with the WMA Section 5.3.2.4: Flood Risk Profile has been updated
 - Components of the final landforms with potential reviewed (**Flood Assessment report - Appendix** assessment peak velocity results for the 0.1% AEP assess the risk of landform erosion under very rare assessment of landform erosion risk from regional
 - Flooding against the rehabilitated final flood velocities in very rare flood events of erosion, particularly with long-term
 - Flood protection landforms have been to the NUMAs. Therefore no flood ingre for all events up to and including the PM
 - The diversions are expected to perform designs and the current creek diversion
 - Rock mulching in discrete locations of the spoil landforms could be considered if increased erosion
 - A new Section **5.3.5.4.4: Areas susceptible to flood** amended PRCP, with further details provided in **Profile**. Rock mulching in discrete locations of the protection landforms could be considered if increased erosion
- b. As mentioned in Appendix J, 300mm soil depth is used, the model will generally limit erosion as there transport off the slope. 300mm is used as a means of this amount (typically with vegetation), then a thinness Sensitivity runs with the model confirmed this.
- The topsoil application rate of 150mm is not alt modelling, as the extra depth was illustrative, no See RFI 18 for further justification of the use of 1
- c. Appendix J notes the relationship between increased rates. The report was making recommendations of p that could be used, and also referred to methods used **Management Strategies to minimise Erosion risks** h outline the actual proposed methodologies that will required.
- d. Appendix J was making recommendations of potential could be used, and also referred to methods used on **Management Strategies to minimise Erosion risks** h outline the actual proposed methodologies that will required.

Insufficient information has been provided to demonstrate that the landform design has considered and addressed the risk of increased erosion at areas where the landform causes flow to concentrate as shown in Figure 5.4 of Appendix J and Figure 3-31 of PRC plan (page 108 of PRCp). The erosion modelling undertaken did not consider concentrated flows, and as a result the findings would be invalid on areas of the landforms that concentrate flow by design. This information is required to demonstrate the final landform is stable.	in rill/gully incision into dispersive spoil materials.	intended to protect the landform from rill/gully incision into dispersive spoil material.
		Furthermore, milestone criteria within the amended PRCP landforms to contain erosion and sediment control systems and fit for purpose, and that reshaped landform have been stable by an AQP. The implementation of such measures whilst groundcover is established.
Erosion assessment Section 5.4 of the Appendix J includes the recommendation to undertake further characterisation and testing of materials to derive more reliable erosion predictions, noting that “Modelling inputs have been derived from existing Fox reports, which have diverse sources. A tailored site-specific sampling program could provide experimentally derived results, using actual site materials where an erosional stress is applied by way of flumes and simulated rainfall.” Erosion predictions should be based on site-specific data to provide sufficient confidence that the proposed landform designs can support the proposed PMLU and will be stable and non-polluting.	28.1 Provide updated PRC plan and Appendix J that includes – a. Updated erosion assessment based on measured, site-specific erodibility rates.	a. Erosion prediction and soil qualities presented within specific data collected through the development of Site Assessment: The Foxleigh Plains Project. HAN19-001 Geochemical characterisation of mining waste, coal, 2021. An updated erosion assessment was not deemed expected that the results of further modelling at this significant change to erosion management. Section 5 to minimise Erosion risks outlines the actual proposals applied at Foxleigh. In addition, extra Milestone criteria have been added to the RM’s.
Landform Topsoil Section 3.3 of the Appendix J states that soil mapping in 2011 found the site was dominated (43%) by brown/yellow sodosols and other smaller areas of different coloured duplex soils and cracking clay vertosols. The three materials considered in WEPP modelling were sodosols, vertosols, and chromosols. Physical properties of the vertosols and sodosols indicate these soils are erosion prone. It is unlikely that WEPP modelling would have considered the dispersive properties of each soil type and cracking behaviour of vertosols. Exclusion of these properties may under-estimate actual soil erosion rates and may not provide reliable final landform stability predictions.	29.1 Provide updated PRC plan and Appendix J that includes – a. Revised WEPP modelling to include potential increased erosion where vertosols and sodosols have been used.	a. A revised WEPP modelling assessment was not deemed assessment did consider properties associated with the were different for the soil types, and the results of the the appropriate erosion control methods, such as % expected that the results of further modelling at this significant change to erosion management.
		Final landform design parameters outlined within section 5 outlined in Section 5.4 have been developed to address a These practices include: - Minimising slopes on newly rehabilitated slopes - Restricting slope lengths to a maximum of 100m - Requiring newly reshaped landforms to conform to systems designed by an AQP, installed, and - Reshaped landform have been assessed as fit for purpose - Inclusion of a cover crops within the seed mix on the exposed surfaces. The implementation of above measures and milestone criteria for rehabilitation, is expected to minimise erosion risks (no more than 10% erosion) and ensure the final landform has a slope erosional stability is achieved once groundcover reaches 80%.
Slope stability Section 4.1 of the Appendix J includes a Table 4.1: WEPP annual average mean soil loss rate outputs (T/ha/Yr) for 0% vegetation cover. The Table 4.1 shows that bare soil conditions and ground cover 60% ground cover. More information is required detailing the way bare slopes be managed prior to 60% vegetation cover establishment. This information is required to demonstrate final landform stability.	30.1 Provide updated PRC plan and Appendix J that includes – a. Management strategies to minimise erosion prior to 60% vegetation cover being established and sustained.	a. Management strategies for managing erosion during rehabilitation described in the new Section 5.3.5.4.3 . The final landform will minimise slopes on newly rehabilitated spoil to a maximum slope lengths to a maximum continuous length of 100m.
		- Milestone criteria within the amended PRCP require the final landform to contain erosion and sediment control systems designed to fit for purpose, and that reshaped landform have been stable by an AQP. - Seed mixes have been developed to include a cover crop to ensure the final landform has a slope erosional stability is achieved once groundcover reaches 80%.

	information is needed if another modelling method such as SIBERIA has been considered for landform assessment. The above information is important as the landform stability issue could be crucial for site given the large area susceptible to erosion such as mine dump area of 4315ha (RA1).	likelihood of permanent riling occurring.	b. The new Section 5.3.5.4.2: Proposed Slopes to reduce erosion has been updated to include management to minimise rill/gully erosion. The final design will include minimise slopes on newly rehabilitated spoil to a maximum continuous length of 10m and sediment control systems designed by an AQP, in addition to that reshaped landform have been assessed as geotechnically sound. mixes have been developed to include a cover crop to protect the exposed surfaces. The implementation of such measures will include protections, whist groundcover is established. In addition, Section 7.4.5.2:Landform and Erosion of the PRC has been updated to include maintenance and contingency methods to be implemented should erosion occur, classified as 'moderate' or 'severe' be identified within the PRC plan.								
design and implementation of the cover system, but no testing or validation of this design is presented. Information on key soil physical (PSA, pb, SMC, K, dispersion index, etc) or chemical (pH, EC, ESP etc) characteristics have not been provided in support of the cover materials selection and performance to satisfy the cover objectives. The Appendix L or section 3.5.6 is not detailed enough and must be supported by following – • SMART completion criteria (e.g., in-situ Ksat, in-situ pb, SMC, allowable drainage through cover base, etc) . • in-field cover trials and/or • modelling. This information is required to assess if the final landform will be non-polluting.	32.1 Provide updated PRC plan and Appendix L that includes – - Description of the proposed cover system design based on physio-chemical characteristics of the proposed cover material. - How the selected cover material characteristics helps to achieve the cover system's performance objectives as stated below: • to minimise recharge of tailings moisture from deep infiltration of rainfall. • to avoid upward movement of leachate from tailings into the vegetation rooting zone; and • to accommodate long-term consolidation settlement in the tailings, such that the first two objectives and surface erosional stability are not compromised. (Refer page 109 of the PRC plan)	Section 5.3.6.2: Potential Cover Materials has been updated to include properties from Fox that are suitable for the cover landform analysis is included. Section 5.3.6.1: Objectives of Cover Design outlines the cover system to meet the objectives of the Cover Design. It should include a contaminant of concern that the cover design is intended to prevent no PAF materials in the tailings materials. Updated milestone criteria within Section 5.10.1 of the appendix to ensure the covers are effectively implemented to achieve the design objectives. NB. Cover trials are not currently feasible on the TSF as the design is in a depositional area. At the end of active deposition, areas of cover will be available for a trial sooner than areas in the middle of the design. Cover given to implementing a trial at that time. Also, it is expected that further preliminary cover design, and it is expected that further research and development in the industry that cover proposed methods.	Section 7.4.2:Landform and Erosion includes the updated Monitoring Criteria. - Erosion monitoring and associated milestone criteria will be implemented with the Australian Soil and Land Survey Field Handbook (Terra 2009).								
Landform and Erosion: Section 3.7.2 states that, 'field-based erosion monitoring should take place annually and erosion severity be ranked using criteria displayed in Table 3-72: Field Erosion Monitoring Criteria.' The PRCP schedule proposes a criteria for erosion control based on Table 3-72 as follows – 'No erosion classification of 'Severe' or 'Extreme' (>30 rills/gullies with average depth of >0.3m) present on site'. The technical basis for Table 3-72 are not clear and does not justify adoption of above-mentioned milestone criteria allowing moderate erosion when compared to the 'Erosion Classification Framework' published by the Australian Soil and Land Survey Field handbook. (refer image below).	Table 1. Erosion classification framework <table border="1"> <thead> <tr> <th>Erosion</th> <th>Minor</th> <th>Moderate</th> <th>Severe</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	Erosion	Minor	Moderate	Severe					33.1 Provide an updated Rehabilitation Planning Part that includes: - Field based erosion monitoring data if available - Justification how the proposed criteria for erosion control likely to meet the safe, stable PMLU.	Section 7.4.2:Landform and Erosion includes the updated Monitoring Criteria. - Erosion monitoring and associated milestone criteria will be implemented with the Australian Soil and Land Survey Field Handbook (Terra 2009).
Erosion	Minor	Moderate	Severe								

	ensure that the final landform is stable and non-polluting into perpetuity, not to ensure compliance with the EA. Groundwater Monitoring: Section 3.7.5 states that groundwater monitoring will be continued in accordance with Schedule E in the EA pending defined trigger limits. The groundwater monitoring and reporting should be done to ensure that the final landform is stable and non-polluting into perpetuity. The reporting requirements in Schedule E of the EA are for the operational phase of the mine and not rehabilitation and closure. The current EA groundwater monitoring network is not considered adequate for post closure phase. Monitoring locations, monitoring frequency, quality characteristics and limits appropriate for rehabilitation and closure need to be defined and included in the PRCP schedule.	and groundwater monitoring locations, monitoring frequency, quality characteristics and limits that are fit for purpose. Please note – - monitoring locations should be based on sources and pathways of potential contamination. - Quality characteristics should be based on CoC. - Limits should be fit for purpose (closure not operation), site-specific and based on Water Quality Objectives, guidelines, and background data.	- Section 5.6.7.3: Groundwater Contaminant of Concern primary contaminant of concern for groundwater - Table 5-14: Potential Contaminants of Concern identifies the monitoring parameters for surface water monitored as part of the Rehabilitation Milestones Existing surface and groundwater monitoring programs have been monitored in consideration of the existing contaminants of concern for transport mechanism and potential resultant environmental closure management of Fox will not introduce any new CoCs, therefore the existing programs are considered to be an appropriate monitoring program to implement post mining.	outline the potential sources of contaminants, contaminants of concern. Further, it outlines the management strategies that have been developed risks. - Section 5.6.7.3: Groundwater Contaminant of Concern primary contaminant of concern for groundwater - Table 5-14: Potential Contaminants of Concern identifies the monitoring parameters for surface water monitored as part of the Rehabilitation Milestones Existing surface and groundwater monitoring programs have been monitored in consideration of the existing contaminants of concern for transport mechanism and potential resultant environmental closure management of Fox will not introduce any new CoCs, therefore the existing programs are considered to be an appropriate monitoring program to implement post mining.	Section 7.4.: Rehabilitation Monitoring Methods has been address this RFI. - To ensure rehabilitation at Fox can demonstrate rehabilitation objectives and outcomes of safe, sustainable polluting, milestone criteria have been developed benchmark criteria or targeted land suitability. - The survey methodologies outlined have been a Herbarium survey technique (<i>Methodology for Surveying Ecosystems and Vegetation Communities in Queensland</i>, al. 2019) and the <i>Method for the Establishment BioCondition</i> (Eyre et al. 2017). Section 5.4.4: Cattle Grazing PMLU lists Milestone Criteria for revegetation relevant to Low Intensity Grazing PMLU have been RM6 - Revegetation (seeding and / or planting). The following RA1, RA3, RA4, RA5, and RA6. The following milestone criteria - Completed seeding using a selection of species listed in Grazing PMLU (Foxleigh Mine, 2023) - Palatable, productive, perennial pasture species - perennial species sown at a seeding rate of 30kg/ha Section 5.4.6 Native Ecosystem PMLU lists Milestone Criteria for include benchmark criteria reflective of characteristics similar to ecosystems 11.3.1 and 11.3.2. - Species identified are consistent with <i>Table 5-19 Corridor PMLU (Foxleigh Mine, 2023)</i>, - Assessment by an AQP that rehabilitation represents with characteristics similar to REs 11.3.1 and 11.3.2. ≥2 tree species ≥3 shrub species ≥ 5 groundcover species	a. A new RA7 has been created for Existing Historical RA7 b. Maps and spatial data have been updated accordingly
	Grazing and Native Ecosystem PMLU monitoring Section 3.7.2 outlines a monitoring schedule and rehabilitation parameters for grazing PMLU. The section does not provide a benchmark against identified rehabilitation parameters to determine safe, stable, non-polluting, and self-sustaining nature of grazing PMLU. Example of benchmark* could be defining grass species richness by identifying the seed mix and application rate, annual grass yield, crown cover etc Table 3-80 does not include parameters for measuring the native tree, shrub species richness, recruitment rate etc. It is recommended that for Native Ecosystem PMLU a BioCondition framework* should be adopted for monitoring benchmark and technique. *BioCondition Matrix – https://www.qld.gov.au/_data/assets/pdf_file/0029/68726/biocondition-assessment-manual.pdf	35.1 Provide an updated Rehabilitation Planning Part that includes: a. Benchmarks to monitor achievement of cattle grazing and Native Ecosystem PMLU				36.1 Update PRCP schedule – a. To add new RA for existing rehabilitation b. Update maps and spatial data accordingly
Areas	Spatial data shows that existing rehabilitation is included in Mining and Mine Dump Areas (RA1). It is recommended to separate the existing rehabilitation areas from RA1 and be captured					

Retained infrastructure. The PRCP schedule does not provide any rehabilitation milestone suitable for retained infrastructure and explaining the steps that are required to ensure safe, stable stage achieved for retained infrastructure.	38.1 Provide a dedicated rehabilitation milestone criteria suitable for retained infrastructure.	RM12 Achievement of post-mining land use to a stable condition (PMLU) has been created. RM12: Achievement of post-mining land use to a stable condition (PMLU), as (outlined in Table 5-22 in section 5.10.1 of the PMLU), included to ensure this PMLU achieves the definitions of a stable condition. • No infrastructure remaining other than those that are required for the agreement. • The RA is safe with safety hazards, as determined by the RA, and surrounding unmined landscapes. • There is no environmental harm being caused by the retained infrastructure. • Retained water storage water quality for quality objectives for livestock drinking water defined in the (Water) Policy 2009 Mackenzie River Sub-basin Environmental Quality Objectives Basin No. 130 (part), including the Mackenzie River Sub-basin, September 2011, or the most recent version. • All retained water storages achieve geotechnical stability and approved by an AQP. • No evidence of erosion on the retained dam banks or 'severe'. • Dams to remain for landholder use are safe for stock and people on banks.
--	---	---

	Specify the erosion management practices. cover system. d. A corrective measure to ensure cover system meets the benchmark. e. Specify the erosion management practices.	b. Key steps to achieve a successful cover system installation. The following milestone criteria is proposed in RM3: System/Capping: - Low clay content NAF spoil is placed 2m thick - Non-Acid Forming spoil meets the following - Total sulfur >0.1 % - NAPP<-5 kg H2SO4/t) - Acid neutralising capacity: maximum - A low permeability layer ≥ 1m of material (v Tertiary spoil), compacted to at least ten times above it. The surface will be shaped to shed landform. ≤ 2m of gravelly fresh Permian spoil is placed - Final ground surface will shed rainfall without c. Benchmark to measure the performance of cover system. Therefore, the benchmarks to measure the performance of vegetation consistent with the PML demonstrate the achievement of the PMLU have been – Achievement of target post-mining land use to safe Intensity Grazing PMLU). d. A corrective measure to ensure cover system meets Corrective measures for all RM's are detailed within the outlined in Appendix V: Demonstration of Milestone implemented when monitoring identifies issues with milestone criteria are not being met. e. Specify the erosion management practices Erosion management criteria is contained within RM Requirements, and RM8 – Achievement of target post-mining land use to safe Intensity Grazing PMLU) Note: the following changes in numbering of RM's in the - RM4 is the new RM3: Installation of Cover System/Capping
--	---	--

d. Targeted land suitability class	AQP, and any recommendation made for ameliorants to achieve the relevant PMLU. - Gypsum will be applied at a rate determined by recommendations. - Fertiliser to be applied at a minimum rate of 100 kg/ha based on recommendations. - Records of ameliorants applied and incorporated into the AQP. - Records that topsoil placement has achieved a minimum depth of 100mm. - Ripping depth on contour to a minimum of 500mm. Milestone Criteria to address ongoing soil quality in rehabilitation proposed to be included in RM7 – Achievement of Surface Rehabilitation applicable for all RA's involving revegetation. The following milestones are proposed: - Soil testing (sampled 12 months and 5 years after the rehabilitation was completed where required) indicates the following parameters for post-mine land suitability (Short 2023): - Plant Available Water Capacity (PAWC); 30 - < 40 mmol/L - Bicarbonate P (at 0 -10cm depth); 4 - <8 mg/l - Electrical Conductivity (1:5 dilution) (in the root zone) < 0.5 dS/m . - Soil pH as measured at any part of the root zone > 4.5 - Exchangeable Sodium Percentage (ESP%) (at 0-10cm depth) - Slope <10%, ESP <14% - Slope >10%, ESP <6% Note: the following changes in numbering of RM's in the table are proposed: - RM6, RM7, and RM8 have been combined into the new RM6 (topsoil)
---	---

	• Completed seeding using a selection of species listed in Grazing PMLU (Foxleigh Mine, 2023) • Palatable, productive, perennial pasture species sown at a seeding rate of 30kg/ha Milestone Criteria to address the establishment of revegetation Grazing PMLU have been proposed to be included in RM6 - Revegetation (seeding and / or planting). The following criteria will be applicable for RA1 following milestone criteria is proposed: • Completed seeding using a selection of species listed in Grazing PMLU (Foxleigh Mine, 2023) • Palatable, productive, perennial pasture species sown at a seeding rate of 30kg/ha Milestone Criteria to address the establishment of revegetation have been proposed to be included in RM6 - Revegetation (seeding and / or planting) will be applicable for RA5: • Native tree and shrub species mix sown suit a native characteristics similar to REs 11.3.1 and 11.3.2. • Completed seeding using a selection of species listed in <i>Native Ecosystem Corridor PMLU (Foxleigh Mine, 2023)</i> • Seeding selection includes a minimum of: • Six upper story native species sown at a seeding rate of 1kg/ha • Five mid-stratum native species, at a seeding rate of 1kg/ha • Five lower story shrub and grass species at a seeding rate of 1kg/ha • Two legumes at a seeding rate of 1kg/ha. Milestone Criteria to address the establishment of revegetation have been proposed to be included in RM6 - Revegetation (seeding and / or planting) will be applicable for RA8: • Completed seeding using a selection of species listed in Grazing PMLU. • Grass species mix sown with a minimum of 4 perennial species at a seeding rate of 30kg/ha. Note: the following changes in numbering of RM's in the following criteria will be applicable for RA8: • RM9, RM10, and RM11 have been combined into the following criteria: (seeding and / or planting)
--	---

the proposed plan section. Stakeholders to further assessment of permanent and temporary diversions against the ACARP stability criteria which is not reflected in the schedule.	c. Include a criterion to assess stability of the permanent diversions.	Instead, To ensure rehabilitation at Fox can demonstrate rehabilitation objectives and outcomes of safe, stable milestone criteria have been developed based on either criteria or targeted land suitability. RM7 has the following alternative criteria: Low Intensity Grazing PMLU • Pasture species identified are consistent with Grazing PMLU • At least 4 perennial species established Novel Native Ecosystem PMLU • Assessment by an AQP that rehabilitation ecosystem with characteristics similar to ▪ ≥2 tree species ▪ ≥3 shrub species ▪ ≥ 5 groundcover species b. Weed criteria: The following criteria has been added into RM8, RM9 and RM7. However, weed monitoring will be included in a weed control will be implemented at all stages of rehabilitation. • Weed presence, as defined in the Biosecurity Act, 10% of total vegetative groundcover cover in monitoring report with weed management plan c. Stability of creek diversions: The following criteria has been added into RM9 rather than RM8. Monitoring will be included in all vegetation monitoring implemented at all stages of rehabilitation. • Assessment by an AQP that the Diversion has an acceptable Criteria for functioning river landscape units in the ACARP Project number C20017). Note: the following changes in numbering of RM's in the ACARP Project number C20017, and RM14 have been combined into the following surface requirements. • RM8: Achievement of post-mining land use to a stable grazing PMLU). • RM9: Achievement of post-mining land use to a stable grazing PMLU) • RM10: Achievement of post-mining land use to a stable ecosystem PMLU) • RM11: Achievement of post-mining land use to a stable ecosystem PMLU)
---	--	---

	• Does not provide monitoring locations/frequency and benchmark/standard for water quality assessment. • No criteria for soil testing.		c. Benchmark against which the surface water quality will be measured. d. Soil testing criteria to support self-sustaining PMLU.	b. Surface water quality monitoring locations, frequency has been added in each of the RM's: • Receiving waters water quality monitoring results Table 7 and Table 10 water quality triggers, which locations outlined in Table 11 or are comparable of at least two years. c. Benchmark for surface water – as per b. d. Soil testing criteria • Soil testing (undertaken 5 yearly (or a lesser period) following parameters are met for the relevant period 2023): • Plant Available Water Capacity (PAWC); 30 - • Bicarbonate P (at 0 -10cm depth); 4 - <8 mg • Electrical Conductivity (1:5 dilution) (in the range 0 - 1000 dS/m). • Soil pH as measured at any part of the root zone • Exchangeable Sodium Percentage (ESP%) (a range of 0 - 15) ○ Slope <10%, ESP <14% ○ Slope >10%, ESP <6% Note: the following changes in numbering of RM's in the table have been made: • RM15 is now RM8: Achievement of post-mining land use intensity cattle grazing PMLU. • RM16 is now RM9: Achievement of post-mining land use intensity watercourse PMLU • RM17 is now RM10: Achievement of post-mining land use intensity native ecosystem PMLU New relevant RM with the same criteria are: • RM11: Achievement of post-mining land use to a standard PMLU)
		44.1 Provide an updated PRCP Schedule to include SMART criteria regarding – a. Slope geometry for each residual void b. Factor of safety for each void	44.1 Provide an updated PRCP Schedule to include SMART criteria regarding – a. Slope geometry for each residual void b. Factor of safety for each void	The PRCP milestone and schedule have been updated to include SMART Criteria to address the landform stability relevant to the proposed to be included in: MM1 – Achievement of structural stability, MM1 will be updated to include: a. Slope geometry • Void walls / slopes assessed as stable by an AQP • Overall, in-situ pit wall and floor slopes <275% (<275% for voids) • Overall backfilled spoil walls and floor within the void b. Factor of Safety • In-situ pit walls ,floor and backfilled spoil within the void meeting an FOS>1.5.

the following steps required to determine its effectiveness: - The EA Appendix 2 states that all residual voids to be protected by permanently rehabilitated stable flood protection landforms. The provided criteria refers to abandonment safety bund and a safety bund, but it is not clear if they are meant to qualify as flood protection landform. - The criteria for abandonment safety bund rehabilitation does not specify the steps to be followed to achieve the self-sustaining rehabilitation such as application of topsoil, growth media application etc. Further vegetation species and seeding rates have not been included.	floor slopes and walls. - Specification to establish an appropriate drainage system and criteria to determine success. - Landform design specification for permanent flood protection landforms providing protection for 0.1%AEP. - Abandonment safety bund rehabilitation steps	that will be safe and structurally stable, includes the - Modelling confirms that residual void acts as a good environment into perpetuity Note: as pit lake equilibrium is not modelled to be reached does not seem reasonable to propose a specific pit water monitoring seeks to confirm the modelling over time. b. Stability Milestone Criteria to address erosion/stability within NUNM be included in: MM2 – Achievement of landform design and surface applicable for all IAs. The following milestone criteria - Evidence has shown ground cover between the void >60% where ground cover is defined as any cover and may include live cover. - Results have shown that, between the void crest erosion features are not present and that any initial vegetation cover. c. Drainage MM3 - Achievement of sufficient improvement not that will be safe and structurally stable, includes the - Final void walls confirmed to drain internally d. Flood Protection MM2 – Achievement of landform design and surface applicable for all IAs. The following milestone criteria - An AQP has certified that NUMA is immune e. Abandonment Bund MM2 – Achievement of landform design and surface applicable for all IAs. The following milestone criteria - Safety infrastructure established around the void - cattle exclusion zone to prevent cattle access - adequate bunding in place confirmed to appropriately qualified person; - perimeter fencing and signage erected to humans; and - appropriate signage placed every 100 m clearly identify and convey the purpose Management Area No Entry). - Bunding constructed to the following design criteria (Flood Protection Landform): - a minimum batters 1V:3H - a minimum height of 2 m; and - located at least 25 m beyond the area of instability of the pit edge.
--	---	--

		MM3 - Achievement of sufficient improvement not to cause that will be safe and structurally stable, includes the following: • Modelling confirms that residual void acts as a groundwater environment into perpetuity • Groundwater monitoring confirms modelling of five (5) year monitoring program. • Groundwater monitoring locations and frequency program outlined in the EA (EPML00744813) • Groundwater monitoring results are within triggering (EPML00744813). NOTE: as an amendment to the EA to address groundwater submitted soon, no specific table references are made in be amended. It is considered that the most relevant criteria for post-climate monitoring that confirms the groundwater and void models remain as a groundwater sink, and therefore presents no groundwater.
--	--	--

20240530_PRCP V1.2_RFI Response to DES

Final Audit Report

2024-05-30

Created:	2024-05-30
By:	Celeste Ellice (cellice@foxleighmine.com)
Status:	Signed
Transaction ID:	CBJCHBCAABAAMZWpEucNH2QKriM6ZWwsS2IG4PJArjx2Z

"20240530_PRCP V1.2_RFI Response to DES" History

-  Document created by Celeste Ellice (cellice@foxleighmine.com)
2024-05-30 - 0:10:07 AM GMT
-  Document emailed to Andrew Boyd (aboyd@qmetco.com.au) for signature
2024-05-30 - 0:10:14 AM GMT
-  Email viewed by Andrew Boyd (aboyd@qmetco.com.au)
2024-05-30 - 0:11:44 AM GMT
-  Document e-signed by Andrew Boyd (aboyd@qmetco.com.au)
Signature Date: 2024-05-30 - 0:12:04 AM GMT - Time Source: server
-  Agreement completed.
2024-05-30 - 0:12:04 AM GMT