

Permit

Environmental Protection Act 1994

Environmental Authority EPML00739113 Lake Lindsay Coal Mine

This environmental authority is issued by the administering authority under Chapter 5 of the Environmental Protection Act 1994.

Environmental authority number: EPML00739113

Environmental authority takes effect on 1 May 2026.

The anniversary date of this environmental authority is 18 June each year. The payment of the annual fee will be due each year on this day.

Environmental authority holder(s)

Name(s)	Registered address
Anglo Coal (German Creek) Pty Ltd	Level 11, 201 Charlotte St, BRISBANE QLD 4000
Jena Pty Limited	Level 11, 201 Charlotte St, BRISBANE QLD 4000
Mitsui German Creek Investment Pty Ltd	Level 46, Gateway, 1 Macquarie Place, SYDNEY NSW 2000

Environmentally relevant activity and location details

Environmentally relevant activity/activities	Location(s)
Resource Activity, Schedule 3 – 13: Mining black coal	ML70336 ML700076
Ancillary Activity, Schedule 2 – 08: Chemical Storage 3 - Storing more than 500 cubic metres of chemicals of class C1 or C2 combustible liquids under AS 1940 or dangerous goods class 3 under subsection (1)(c)	
Ancillary Activity, Schedule 2 – 16: Extraction and Screening 3(c) - Screening, in a year, the following quantity of material - more than 1,000,000t	
Ancillary Activity, Schedule 2 – 62 - Resource recovery and transfer facility operation 1(c) - Operating a facility for receiving and sorting, dismantling, baling or temporarily storing category 2 regulated waste	
Ancillary Activity, Schedule 2 – 62 - Resource recovery and transfer facility operation 1(d) - Operating a facility for receiving and sorting, dismantling, baling or temporarily storing category 1 regulated waste	
Ancillary Activity, Schedule 2 – 63 - Sewage Treatment 1(b-i) - Operating sewage treatment works, other than no-release works, with a total daily peak design capacity of more than 100 but not more than 1500EP if treated effluent is discharged from the works to an infiltration trench or through an irrigation scheme	

Additional information for applicants

Environmentally relevant activities

The description of any environmentally relevant activity (ERA) for which an environmental authority (EA) is issued is a restatement of the ERA as defined by legislation at the time the EA is issued. Where there is any inconsistency between that description of an ERA and the conditions stated by an EA as to the scale, intensity or manner of carrying out an ERA, the conditions prevail to the extent of the inconsistency.

An EA authorises the carrying out of an ERA and does not authorise any environmental harm unless a condition stated by the EA specifically authorises environmental harm.

A person carrying out an ERA must also be a registered suitable operator under the *Environmental Protection Act 1994* (EP Act).

Mobile and temporary activities

If you operate a mobile and temporary environmentally relevant activity (ERA), other than regulated waste transport, you are required to maintain a work diary. You must:

- use the approved form for a work diary (ESR/2015/1696);
- keep the work diary records for 2 years after the last entry;
- inform the administering authority within 7 days of the work diary being lost or stolen;
- record the information required in the work diary for each location within 1 day of leaving the location.

Contaminated land

It is a requirement of the EP Act that an owner or occupier of land give written notice to the administering authority if they become aware of the following:

- the presence of, or happening of an event involving, a hazardous contaminant on the land that is causing, or is reasonably likely to cause, serious or material environmental harm (notice must be given within 24 hours); or
- if the land is contaminated land – a change in the condition of the land that is causing, or is reasonably likely to cause, serious or material environmental harm (notice must be given within 24 hours); or
- a notifiable activity (as defined in Schedule 3) having been carried out, or is being carried out, on the land (notice must be given within 20 business days).

For further information, including the form for giving written notice, refer to the Queensland Government website www.qld.gov.au, using the search term 'duty to notify'.

Take effect

Please note that, in accordance with section 200 of the EP Act, an EA has effect:

- a) if the authority is for a prescribed ERA and it states that it takes effect on the day nominated by the holder of the authority in a written notice given to the administering authority – on the nominated day; or
- b) if the authority states a day or an event for it to take effect – on the stated day or when the stated event happens; or
- c) otherwise – on the day the authority is issued.

However, if the EA is authorising an activity that requires an additional authorisation (a relevant tenure for a resource activity, a development permit under the *Planning Act 2016* or an SDA Approval under the *State Development and Public Works Organisation Act 1971*), this EA will not take effect until the additional authorisation has taken effect.

If this EA takes effect when the additional authorisation takes effect, you must provide the administering authority written notice within 5 business days of receiving notification of the related additional authorisation taking effect.

If you have incorrectly claimed that an additional authorisation is not required, carrying out the ERA without the additional authorisation is not legal and could result in your prosecution for providing false or misleading information or operating without a valid environmental authority.

Burgess

Signature

01 May 2026

Date

Emma Burgess

Enquiries:

Department of the Environment, Tourism, Science and Innovation
Delegate of the administering authority
Environmental Protection Act 1994

Coal Business Centre
PO Box 3028, Emerald QLD 4720
Phone: (07) 4987 9320
Email: CRMining@detsi.qld.gov.au

Obligations under the *Environmental Protection Act 1994*

In addition to the requirements found in the conditions of this environmental authority, the holder must also meet their obligations under the EP Act, and the regulations made under the EP Act. For example, the holder must comply with the following provisions of the Act:

- general environmental duty (section 319)
- duty to notify environmental harm (section 320-320G)
- offence of causing serious or material environmental harm (sections 437-439)
- offence of causing environmental nuisance (section 440)
- offence of depositing prescribed water contaminants in waters and related matters (section 440ZG)
- offence to place contaminant where environmental harm or nuisance may be caused (section 443).

Other permits required

This permit only provides an approval under the *Environmental Protection Act 1994*. In order to lawfully operate you may also require permits / approvals from your local government authority, other business units within the department, and other State and Federal Government agencies prior to commencing any activity at the site. For example, this may include permits / approvals with your local Council (for planning approval), the Department of Transport and Main Roads (to access State controlled roads), the Department of Natural Resources and Mines, Manufacturing, and Regional and Rural Development (to clear vegetation), and the Department of Primary Industries (to clear marine plants or to obtain a quarry material allocation).

Obligations under the *Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act)

Matters of national environmental significance (MNES) are regulated under the Commonwealth EPBC Act rather than under state legislation. You may need to submit a referral if your project potentially impacts any matters protected under the EPBC Act. For more information on self-assessments, and referral and assessment processes please visit the Department of Climate Change, Energy, the Environment and Water webpage, <https://www.dcceew.gov.au/environment/epbc/advice>.

Obligations under the *Mining and Quarrying Safety and Health Act 1999*

If you are operating a quarry, other than a sand and gravel quarry where there is no crushing capability, you will be required to comply with the *Mining and Quarrying Safety and Health Act 1999*. For more information on your obligations under this legislation contact Mine Safety and Health at <https://www.nrmrdd.qld.gov.au/>, or phone 13 QGOV (13 74 68) or your local Mines Inspectorate Office.

Obligations under the *Aboriginal Cultural Heritage Act 2003* and *Torres Strait Islander Cultural Heritage Act 2003* (the Cultural Heritage Acts)

The Cultural Heritage Acts require anyone who carries out a land-use activity to exercise a duty of care. This 'duty of care' means land users must take all reasonable and practicable measures to ensure their activity does not harm Aboriginal or Torres Strait Islander cultural heritage, and applies to any activity where Aboriginal or Torres Strait Islander cultural heritage is located. For more information on your obligations under this legislation, please visit the Department of Women, Aboriginal and Torres Strait Islander Partnerships and Multiculturalism webpage at, <https://www.dwatsipm.qld.gov.au/>.

Conditions of environmental authority

The environmentally relevant activities conducted at the locations as described above must be conducted in accordance with the following site-specific conditions of approval. This environmental authority consists of the following Schedules:

- Schedule A – General
- Schedule B – Air
- Schedule C – Surface Water
- Schedule D – Regulated Structures
- Schedule E – Acoustic
- Schedule F – Waste Management
- Schedule G – Land
- Schedule H – Groundwater
- Schedule I – Biodiversity
- Definitions
- Appendices

Schedule A – General	
Condition No.	Condition
A1	Maintenance of measures, plant and equipment The environmental authority holder must ensure that (a) All measures, plant and equipment necessary to ensure compliance with the conditions of this environmental authority are installed, operated, maintained and calibrated in a proper manner; and (b) Records of installation, operation, maintenance and calibration carried out under condition A1 must be kept for a minimum of 5 years.
A2	Monitoring and record keeping The environmental authority holder must keep records of monitoring results required by this environmental authority for a minimum of 5 years.
A3	Upon request from the administering authority, copies of all records, plans and other documentation required by the conditions of this environmental authority must be made available and provided to the administering authority within: (a) 10 business days; or (b) An alternative timeframe agreed between the administering authority and the environmental authority holder.
A4	Spillage of all flammable and combustible liquids must be contained within an on-site containment system and controlled in a manner that prevents environmental harm (other than trivial harm) and maintained in accordance with the most current version of the Australian Standard - <i>Storage and Handling of Flammable and Combustible Liquids</i>.
A5	The environmental authority holder is approved for a coal extraction rate of up to but not exceeding 6.5 million tonnes per annum (Mtpa) of run-of-mine (ROM) ore.
A6	Authorised disturbance Disturbance is authorised as shown in Appendix 1 Authorised Disturbance Area, including: (a) Surface Disturbance within areas marked as “Approved Surface Disturbance”; and (b) Sub-surface Disturbance within areas marked as “Approved Sub-surface Disturbance”.
A7	Any disturbance outside of the areas marked in Appendix 1 Authorised Disturbance Areas: (a) Is only authorised to the extent reasonably necessary for exploration and activities ancillary to the mining activity, including but not limited to roads, fences, underground services, telecommunications facilities, pipelines, electrical infrastructure, storage depots, laydown or shutdown pads, monitoring stations and bores, and disturbance for rehabilitation activities; and (b) Must not result in significant residual impact to prescribed environmental matters.

A8	The environmental authority holder must maintain records of the assessment undertaken in accordance with condition A7(b) demonstrating that each impact to a prescribed environmental matter did not, or is not likely to result, in a significant residual impact to that matter and must be: (a) Completed by an appropriately qualified person; and (b) Kept for the life of the environmental authority.
A9	This environmental authority authorises environmental harm referred to in the conditions. Where there is no condition or this environmental authority is silent on a matter, the lack of a condition or silence does not authorise environmental harm.
A10	All monitoring, sampling, plans, reports, programs and determinations required under the conditions of this environmental authority must be implemented and carried-out by an appropriately qualified person.
A11	Risk management The holder of this environmental authority must implement a risk management system for mining activities which mirrors the content requirement of the Standard for Risk Management (ISO31000:2009), or the latest edition of an Australian standard for risk management, to the extent relevant to environmental management.
A12	The holder of this environmental authority must notify the administering authority by written notification within 24 hours, after becoming aware of any emergency or incident which results in the release of contaminants not in accordance, or reasonably expected to be not in accordance with, the conditions of this environmental authority.
A13	Within 10 business days following the initial notification of an emergency or incident, or receipt of monitoring results, whichever is the latter, further written advice must be provided to the administering authority, including the following: (a) Results and interpretation of any samples taken and analysed; (b) Outcomes of actions taken at the time to prevent or minimise unlawful environmental harm; and (c) Proposed actions to prevent a recurrence of the emergency or incident.
A14	Complaints The following details must be recorded for all complaints received and provided to the administering authority upon request: (a) Date and time the complaint was received; and (b) If authorised by the person making the complaint, their name and contact details; and (c) Nature and details of the complaint.
A15	As soon as reasonably practicable but no later than 20 business days (or a longer period agreed to in writing by the administering authority) of receiving a complaint, which is neither frivolous nor vexatious, an investigation must be undertaken to determine: (a) The potential circumstances and actions on site that may have contributed to the basis of the complaint; and (b) Any reasonable and practicable measures that will be implemented to address the complaint.
A16	As soon as reasonably practicable but no later than 10 business days of investigating a complaint under condition A15 (or a longer period agreed to in writing by the administering authority), any reasonable and practicable measures identified in the investigation must be implemented.

A17	The outcome of the investigation carried out under condition A15 and any reasonable and practicable measures implemented under condition A16 , respectively must be recorded.
A18	Third-party reporting The holder of this environmental authority must: (a) Within one year of the commencement of this environmental authority, obtain from a third-party appropriately qualified person, a report on compliance with the conditions of this environmental authority; and (b) Obtain further such reports at regular intervals, not exceeding three yearly intervals, from the completion of the report referred to above; and (c) Provide each report to the administering authority within 90 days of its completion.
A19	Where a condition of this environmental authority requires compliance with a standard, policy or guideline published externally to this environmental authority and the standard is amended or changed subsequent to the issue of this environmental authority, the holder of this environmental authority must: (a) Comply with the amended or changed standard, policy or guideline within 2 years of the amendment or change being made, unless a different period is specified in the amended standard or relevant legislation, or where the amendment or change relates specifically to regulated structures referred to in Schedule D: Regulated Structures the time specified in that condition; and (b) Until compliance with the amended or changed standard, policy or guideline is achieved, continue to remain in compliance with the corresponding provision that was current immediately prior to the relevant amendment or change

Schedule B – Air	
Condition No.	Condition
B1	Dust Nuisance The release of dust or particulate matter or both resulting from the mining activity must not cause an environmental nuisance, or an exceedance of the limits in Table B1 Air quality limits and monitoring requirements, at any sensitive or commercial place. The measurement of air emissions for a sensitive place or commercial place is either: (a) At that place (if measured there); or (b) At the monitoring location representative (whether by reason of correlation or otherwise) of the sensitive place or commercial place (where there is no measure at the sensitive place or commercial place).
B2	Dust and particulate matter monitoring When requested by the administering authority, dust and particulate monitoring must be undertaken within a reasonable and practicable timeframe nominated by the administering authority to investigate any complaint (which is neither frivolous nor vexatious nor based on mistaken belief in the opinion of the authorised officer) of environmental nuisance at any sensitive or commercial place, and the results must be notified within 10 business days to the administering authority following the completion of monitoring.
B3	Air emissions and meteorological conditions must be monitored in accordance with Table B1 Air quality limits and monitoring requirements .
B4	Air Emissions Management Plan (AEMP) An AEMP must be developed by an appropriately qualified person and implemented for the duration of mining activities. The AEMP must incorporate a program for continuous improvement for the management of dust and particulate matter resulting from the mining activities including, but not limited to: (a) The collection of air quality and meteorological data at locations and using the monitoring methods described in Table B1 Air quality limits and monitoring requirements at all locations specified in Table B2 Dust and Particulate Matter Monitoring Locations; (b) A system to identify adverse meteorological conditions likely to produce elevated levels of dust including PM10 at a sensitive place or commercial place due to the mining activities; and (c) A dust and particulate matter control strategy which activates a timely implementation of management control actions.
B5	The AEMP required by condition B4 must be reviewed by 30 September every 2 years by an appropriately qualified person and any recommendations incorporated into the AEMP.
B6	Continuous monitoring The environmental authority holder must conduct continuous air monitoring as per Table B1 Air quality limits and monitoring requirements at the locations detailed in Table B2 Dust and Particulate Matter Monitoring Locations.

B7	The monitoring in accordance with condition B6 must commence: (a) For Stage one, by 31 July 2025; and (b) For Stage two, by 31 March 2026. Note: Stage one and two are as detailed in Table B2 Dust and Particulate Matter Monitoring Locations and the AEMP (version 1, 2024) required by condition B4 of this environmental authority.
B8	Where monitoring identifies instances where a concentration specified in Table B1 Air quality limits and monitoring requirements is exceeded at any sensitive place or commercial place, the environmental authority holder must report to the administering authority within 10 business days: (a) The air quality data at the sensitive place or commercial place; (b) A description of meteorological conditions recorded in accordance with Table B1 Air quality limits and monitoring requirements and Table B2 Dust and Particulate Matter Monitoring Locations occurring at the time; (c) The air quality data upwind of the mining activities (if known); (d) Measures taken to reduce dust generated by the mining activities; and (e) The contribution of the mining activities to the PM10 concentration at the sensitive or commercial place.
B9	All air quality monitoring data must be made publicly available on the environmental authority holders website, in a format agreed to by the administering authority, and updated: (a) For PM10 on a fortnightly basis; and (b) For dust deposition on a monthly basis.
B10	The format of the information to be made available in accordance with condition B9 must be provided to the administering authority for agreement by 2 August 2025.
B11	The environmental authority holder must implement the requirements of condition B9 by 27 September 2025.
B12	Odour The release of noxious or offensive odour(s) or any other noxious or offensive airborne contaminant(s) resulting from the mining activity must not cause an environmental nuisance at any sensitive or commercial place.

Table B1 Air quality limits and monitoring requirements

Monitoring Location	Air Quality Indicator	Frequency	Air Quality Limit	Monitoring Method
All sites as specified in Table B2 Dust and Particulate Matter Monitoring Locations	PM ₁₀	Continuous	50µg/m ³ (24-hr avg)	AS/NZS 3580.9.6:2015 AS/NZS3580.9.7:2009 AS3580.9.8:2022 AS358.9.9:2017 AS/NZS35801.9.11:2022
	Dust deposition	Continuous	120mg/m ² /day	AS/NZS3580.10.1:2003
	Wind speed and direction, Temperature, Precipitation, Relative humidity	Continuous	NA	AS/NZS 3850.14:2014
As per condition B1 and B2	TSP	As per condition B2	90µg/m ³	AS/NZS 3580.9.3:2015 Any alternative method of monitoring TSP that may be permitted by the Air Quality Sampling Manual ¹ as published from time to time by the administering authority.

¹ The State of Queensland Department of Environment (1997) Air Quality Sampling Manual.

Table B2 Dust and Particulate Matter Monitoring Locations

Monitoring Point	Receiving Area	Latitude (decimal degree, GDA94)	Longitude (decimal degree, GDA94)	Monitoring Description
Stage one – to be implemented by 31 March 2025 as per condition B7(a)				
Mount Stuart	Neighbouring Property	148.680541	-23.073195	PM10
Mount Stuart	Neighbouring Property	148.680541	-23.073195	Depositional Dust
Lake Lindsay Weather Station	Mining Lease	148.726506	-22.993304	Weather Station
Lake Lindsay Mine Site – trend ¹	Mining lease – upwind of mine operations under prevailing winds	148.764569	-23.013951	PM10
Lake Lindsay Mine Site – trend ¹	Mining lease – upwind of mine operations under prevailing winds	148.764569	-23.013951	Depositional Dust
Stage two – to be implemented by 31 March 2026 as per condition B7(b)				
Oak Park	Neighbouring Property	TBC – close to Oak Park homestead	TBC	Depositional Dust
Mt Stuart/ Oak Park Indicative site	Closer to mining operations than homesteads to support TARP	TBC	TBC	PM10
Mt Stuart/ Oak Park Indicative site	Closer to mining operations than homesteads to support TARP	TBC	TBC	Depositional Dust

Note to Table B2:

¹this is a trend monitoring station only, not for compliance.

Schedule C – Surface Water	
Condition No.	Condition
C1	Contaminant release Contaminants that will or have the potential to cause environmental harm must not be released directly or indirectly to any waters as a result of the authorised mining activities, except as permitted under the conditions of this environmental authority.
C2	Unless otherwise permitted under the conditions of this environmental authority, the release of mine affected waters to waters must only occur from the release points specified in Table C1 Mine affected water release points, sources and receiving waters and depicted in Appendix 2 Release Points and Monitoring Points for Lake Lindsay Mine attached to this environmental authority.
C3	The release of mine affected water to internal water management infrastructure that is installed and operated in accordance with a water management plan that complies with condition C33 is permitted.
C4	The release of mine affected water to waters in accordance with condition C2 must not exceed the release limits stated in Table C2 Mine affected water release limits when measured at the monitoring points specified in Table C1 Mine affected water release points, sources and receiving waters for each quality characteristic.
C5	The release of mine affected water to waters from the release points must be monitored at the locations specified in Table C1 Mine affected water release points, sources and receiving waters for each quality characteristics and at the frequency specified in Table C2 Mine affected water release limits and Table C3 Release contaminant trigger investigation levels. <i>Note: The administering authority will take into consideration any extenuating circumstances prior to determining an appropriate enforcement response in the event condition C5 is contravened due to a temporary lack of safe or practical access. The administering authority expects the environmental authority holder to take all reasonable and practicable measures to maintain safe and practical access to designated monitoring locations.</i>

Table C1 Mine affected water release points, sources and receiving waters

Release Point (RP)	Latitude (decimal degree, GDA94)	Longitude (decimal degree, GDA94)	Mine affected water source and location	Mine affected water monitoring location	Stream flow monitoring point	Receiving waters description
RP5	-23.048364	148.769952	Lake Lindsay Pits (X1, X2, X3, X4), Highwall dams in the Lake Lindsay mining area, Central Storage Dam, Oak Park Pits (V and W) via Central Storage Dam.	Sample tap on release line at RP5 (adjacent to X4) enables sampling of all waters discharged through this release point.	Oaky Creek Upstream (U/S)	Oaky Creek

Table C2 Mine affected water release limits

Quality Characteristic	Release Limits	Monitoring frequency	Comment
Electrical conductivity (µS/cm)	10,000	Daily during release (the first sample must be taken within 2 hours of commencement of release)	
pH (pH Unit)	6.5 (minimum) 9.0 (maximum)	Daily during release (the first sample must be taken within 2 hours of commencement of release)	
Turbidity (NTU)	Turbidity limit for discharge of mine water from all release points is defined as being equal to or less than the upstream turbidity value for the receiving waters. ^[A] and ^[B]	Daily during release ^[A] (the first sample must be taken within 2 hours of commencement of release)	Turbidity is required to assess ecosystems impacts and can provide instantaneous results.
Total Suspended Solids (mg/L)	No limit ^[B]	Daily during release ^[A] (the first sample must be taken within 2 hours of commencement of release)	Suspended solids are required to measure the performance of sediment and erosion control measures.
Sulfate (mg/L)	3,000	First sample within 2 hours of commencement of release. Weekly thereafter ^[A]	Drinking water environmental values from NHMRC 2006 guidelines or ANZECC.
Note: [A] This condition is approved with the implementation of sediment and erosion control measures to manage onsite stormwater. [B] Data relating to the correlation between turbidity and suspended solids must be recorded and kept for a period of at least 2 years.			

Table C3 Release contaminant trigger investigation levels

Quality Characteristic	Trigger Levels (µg/L)	Comment on Trigger Level	Monitoring Frequency
Aluminium	55	For aquatic ecosystem protection, based on SMD guideline	Commencement of release and thereafter weekly during release
Cadmium	0.2	For aquatic ecosystem protection, based on SMD guideline	
Chromium	1	For aquatic ecosystem protection, based on SMD guideline	
Copper	2	For aquatic ecosystem protection, based on LOR for ICPMS	
Iron	300	For aquatic ecosystem protection, based on low reliability guideline	
Nickel	11	For aquatic ecosystem protection, based on SMD guideline	
Zinc	8	For aquatic ecosystem protection, based on SMD guideline	
Boron	370	For aquatic ecosystem protection, based on SMD guideline	
Cobalt	90	For aquatic ecosystem protection, based on low reliability guideline	
Manganese	1900	For aquatic ecosystem protection, based on SMD guideline	
Molybdenum	34	For aquatic ecosystem protection, based on low reliability guideline	
Uranium	1	For aquatic ecosystem protection, based on LOR for ICPMS	
Ammonia	900	For aquatic ecosystem protection, based on SMD guideline	
Total Petroleum Hydrocarbons (C6-C9)	20		
Total Petroleum Hydrocarbons (C10-C36)	100		
<i>Note:</i> All metals and metalloids must be measured as total (unfiltered) and dissolved (filtered). Trigger levels for metal/metalloids apply if dissolved results exceed trigger. The quality characteristics required to be monitored as per Table C3 Release contaminant trigger investigation levels can be reviewed once the results of 2 years monitoring data is available and it may be determined that a reduced monitoring frequency is appropriate or that certain quality characteristics can be removed from Table C3 Release contaminant trigger investigation levels by amendment.			

C6	If quality characteristics of the release exceed any of the trigger levels specified in Table C3 - Release contaminant trigger investigation levels during a release event, the environmental authority holder must compare the downstream results in the receiving waters to the trigger values specified in Table C3 - Release contaminant trigger investigation levels and: (1) where the trigger values are not exceeded then no action is to be taken; or (2) where the downstream results exceed the trigger values specified Table C3 for any quality characteristic, compare the results of the downstream site to the data from background monitoring sites and; (a) if the result is less than the background monitoring site data, then no action is to be taken; or (b) if the result is greater than the background monitoring site data, complete an investigation into the potential for environmental harm and provide a written report to the administering authority in the next annual return, outlining: (i) details of the investigations carried out; and (ii) actions taken to prevent environmental harm. <i>Note: Where an exceedance of a trigger level has occurred and is being investigated, in accordance with C6(2)(b) of this condition, no further reporting is required for subsequent trigger events for that quality characteristic.</i>
C7	If an exceedance in accordance with condition C6(2)(b) is identified, the holder of the authority must notify the administering authority within fourteen (14) days of receiving the result.
C8	Mine affected water release events The holder must ensure a stream flow gauging station/s is installed, operated and maintained to determine and record stream flows at the locations and flow recording frequency specified in Table C4 - Mine affected water release during flow events.

Table C4 Mine affected water release during flow events

Receiving waters/ stream	Release Point (RP)	Monitoring Point (MP)	Monitoring Point Latitude (decimal degree, GDA94)	Monitoring Point Longitude (decimal degree, GDA94)	Receiving Water Flow Recording Frequency	Receiving Water Flow Criteria for discharge (cubic metres per second) [A]
Oaky Creek	RP5	Oaky Creek Downstream (D/S)	-23.05150	148.77383	Continuous (minimum daily)	0.5

Note: [A] Receiving water flow criteria for discharge and maximum release rates should be reviewed at a minimum of 2 years from the approval date and bi-annually thereafter.

C9	Notwithstanding any other condition of this environmental authority, the release of mine affected water to waters in accordance with condition C2 must only take place during periods of natural flow events in accordance with the receiving water flow criteria for discharge specified in Table C4 Mine affected water release during flow events for the release point(s) specified in Table C1 Mine affected water release points, sources and receiving waters .
C10	The releases of mine affected water to waters in accordance with condition C2 must not exceed a maximum release rate for all combined release point flows of 2m ³ /s.
C11	The electrical conductivity (EC) values recorded at the downstream monitoring points on Oaky Creek must not exceed 2000µS/cm at any time during the release influence period.
C12	The EC values recorded at the Barwon Park monitoring station on Roper Creek must not exceed 1500µS/cm at any time during the release influence period.
C13	If EC recorded at Bingegang Weir exceeds 650µS/cm during a release event, the environmental authority holder must immediately notify the administering authority and seek written approval to continue releasing mine affected water.
C14	The daily quantity of mine affected water released from each release point must be measured and recorded at the monitoring points in Table C1 Mine affected water release points, sources and receiving waters and Table C4 Mine affected water release during flow events .
C15	Releases to waters must be undertaken so as not to cause erosion of the bed and banks of the receiving waters or cause a material build-up of sediment in such waters.

C16	Notification of Release Event The environmental authority holder must notify the administering authority via either the WaTERS online reporting system or via the WaTERS email (psd.help@detsi.qld.gov.au) as soon as practicable and no later than 24 hours after commencing to release mine affected water to the receiving environment. Notification must include the submission of written advice to the administering authority of the following information: (a) Release commencement date/time; (b) Expected release cessation date/time; (c) Release point/s; (d) Estimated release flow rate (e) Release volume (estimated); (f) Release quality including pH and electrical conductivity; (g) Receiving water/s including the natural flow rate; and (h) Any details (including available data) regarding likely impacts on the receiving water(s).
C17	The environmental authority holder must notify the administering authority via either the WaTERS online reporting system or via the WaTERS email (psd.help@detsi.qld.gov.au) within 24 hours after cessation of a release event notified under condition C16 and within 28 days provide the following information in writing: (a) Release cessation date/time; (b) Natural flow volume in receiving water; (c) Volume of water released; (d) Details regarding the compliance of the release with the conditions of Agency Interest: Water of this environmental authority (i.e. contamination limits, natural flow, discharge volume); (e) All in-situ water quality monitoring results; and (f) Any other matters pertinent to the water release event. <i>Note: Successive or intermittent releases occurring within 24 hours of the cessation of any individual release can be considered part of a single release event and do not require individual notification for the purpose of compliance with conditions C16 and C17, provided the relevant details of the release are included within the notification provided in accordance with conditions C16 and C17.</i>
C18	Notification of Release Event Exceedance If the release limits defined in Table C2 Mine affected water release limits are exceeded, the holder of the environmental authority must notify the administering authority within 24 hours of receiving the results.

C19	The authority holder must, within 28 days of a release that exceeds the conditions of this authority, provide a report to the administering authority detailing: (a) The reason for the release; (b) The location of the release; (c) All water quality monitoring results; (d) Any general observations; (e) All calculations; and, (f) Any other matters pertinent to the water release event.
C20	Monitoring of Water Storage Quality Water storages stated in Table C5 Water storage monitoring must be monitored for the water quality characteristics specified in Table C6 Onsite water storage contaminant limits at the monitoring locations and at the monitoring frequency specified in Table C5 Water storage monitoring.

Table C5 - Water storage monitoring

Water Storage Description	Latitude (GDA94)	Longitude (GDA94)	Monitoring Location	Frequency of Monitoring
Lake Lindsay Industrial Dam	-23.00802	148.71073	Any safe access	Quarterly
Lake Lindsay Farm Dam	-23.04408	148.73122		
Dump Station Sediment Dam	-23.02831	148.72644		
X3 Stockpile Runoff Dam	-23.03906	148.73938		

Table C6 - Onsite water storage contaminant limits

Quality Characteristic	Test Value	Contaminant Limit
pH (pH unit)	Range	>4 and <9 ^[B]
EC (µS/cm)	Maximum	5970 ^[A]
Sulfate (mg/L)	Maximum	1000 ^[A]
Fluoride (mg/L)	Maximum	2 ^[A]
Aluminium (mg/L)	Maximum	5 ^[A]
Arsenic (mg/L)	Maximum	0.5 ^[A]

Cadmium (mg/L)	Maximum	0.01 ^[A]
Cobalt (mg/L)	Maximum	1 ^[A]
Copper (mg/L)	Maximum	1 ^[A]
Lead (mg/L)	Maximum	0.1 ^[A]
Nickel (mg/L)	Maximum	1 ^[A]
Zinc (mg/L)	Maximum	20 ^[A]
Note: ^[A] Contaminant limit based on ANZECC and ARMCANZ (2000) stock water quality guidelines. ^[B] Page 4.2-4.15 of ANZECC and ARMCANZ (2000) Soil and animal health will not generally be affected by water with pH in the range of 4–9. Total measurements (unfiltered) must be taken and analysed for metals and metalloids.		

C21	In the event that water storages defined in Table C5 Water storage monitoring exceed the contaminant limits defined in Table C6 Onsite water storage contaminant limits the holder of the environmental authority must implement measures to prevent access to waters by all livestock.
C22	Receiving Environment Monitoring and Contaminant Trigger Levels The quality of the receiving waters must be monitored at the locations specified in Table C8 Receiving water upstream (U/S) background sites and downstream (D/S) monitoring points for each quality characteristic and at the monitoring frequency stated in Table C7 Receiving waters contaminant trigger levels.

Table C7 - Receiving waters contaminant trigger levels

Quality Characteristic	Trigger Level	Monitoring Frequency
pH	6.5 – 8.5	Daily during the release [A]
Turbidity (NTU)	Mine waters released must not exceed background level.	
Sulfate (mg/L)	250 (Protection of drinking water environmental value)	
Note: [A] Sulfate (mg/L) to be sampled within 2 hours of commencement of a release and at weekly intervals thereafter. Electrical conductivity (EC) trigger levels (µS/cm) for receiving waters are presented in conditions C11, C12 and C13.		

Table C8 Receiving water upstream (U/S) background sites and downstream (D/S) monitoring points

Monitoring Points (MP)	Receiving Waters Location Description	Latitude (decimal degree, GDA94)	Longitude (decimal degree, GDA94)
Upstream Background Monitoring Points			
Oaky Creek U/S	Upstream Oaky Creek	-23.07014	148.74208
Downstream Monitoring Points			
Oaky Creek D/S	Downstream Oaky Creek	-23.05150	148.77383
Barwon Park	Roper Creek at Barwon Park	-23.057	148.888
Note: The data from background monitoring points must not be used where they are affected by releases from other mines.			

C23	If quality characteristics of the receiving water at the downstream monitoring points specified in Table C8 Receiving water upstream (U/S) background sites and downstream (D/S) monitoring points, exceed any of the trigger levels specified in Table C7 Receiving waters contaminant trigger levels during a release event the environmental authority holder must compare the downstream results to the upstream results in the receiving waters and: (1) Where the downstream result is the same or a lower value than the upstream value for the quality characteristic then no action is to be taken; or (2) Where the downstream results exceed the upstream results complete an investigation into the potential for environmental harm and provide a written report to the administering authority in the next annual return, outlining: (a) Details of the investigations carried out; and (b) Actions taken to prevent environmental harm. <i>Note: Where an exceedance of a trigger level has occurred and is being investigated, in accordance with C23(2) of this condition, no further reporting is required for subsequent trigger events for that quality characteristic.</i>
C24	Receiving Environment Monitoring Program (REMP) The environmental authority holder must develop and implement a Receiving Environment Monitoring Program (REMP) to monitor, identify and describe any adverse impacts to surface water environmental values, quality and flows due to the authorised mining activity. This must include monitoring the effects of the mine on the receiving environment periodically (under natural flow conditions) and while mine affected water is being discharged from the site. For the purposes of the REMP, the receiving environment is the waters of Oaky Creek to the Roper Creek junction and connected or surrounding waterways within 10km downstream of the release. The REMP must encompass any sensitive receiving waters or environmental values downstream of the authorised mining activity that will potentially be directly affected by an authorised release of mine affected water.

C25	The REMP must: (a) Assess the condition or state of receiving waters, including upstream conditions, spatially within the REMP area, considering background water quality characteristics based on accurate and reliable monitoring data that takes into consideration temporal variation (e.g. seasonality); and (b) Be designed to facilitate assessment against water quality objectives for the relevant environmental values that need to be protected; and (c) Include monitoring from background reference sites (e.g. upstream or background) and downstream sites from the release (as a minimum, the locations specified in Table C8 Receiving water upstream (U/S) background sites and downstream (D/S) monitoring points); and (d) Specify the frequency and timing of sampling required in order to reliably assess ambient conditions and to provide sufficient data to derive site specific background reference values in accordance with the latest version of Queensland Water Quality Guidelines 2006. This must include monitoring during periods of natural flow irrespective of mine or other discharges; and (e) Include monitoring and assessment of dissolved oxygen saturation, temperature and all water quality parameters listed in Table C2 Mine affected water release limits and Table C3 Release contaminant trigger investigation levels); and (f) Include, where appropriate, monitoring of metals/metalloids in sediments (in accordance with ANZECC and ARMCANZ 2000, BATLEY and/or the most recent version of AS5667.1 Guidance on Sampling of Bottom Sediments); and (g) Include, where appropriate, monitoring of macroinvertebrates in accordance with the AusRivas methodology; and (h) Apply procedures and/or guidelines from ANZECC and ARMCANZ 2000 and other relevant guideline documents; and (i) Describe sampling and analysis methods and quality assurance and control measures; and (j) Incorporate stream flow and hydrological information in the interpretations of water quality and biological data.
C26	A REMP Design Document that addresses each criterion presented in conditions C24 and C25 must be prepared and submitted to the administering authority. Due consideration must be given to any comments made by the administering authority on the REMP Design Document and subsequent implementation of the program.
C27	A report outlining the findings of the REMP, including all monitoring results and interpretations in accordance with conditions C24 and C25 must be prepared annually and made available on request to the administering authority. This must include an assessment of background reference water quality, the condition of downstream water quality compared against water quality objectives, and the suitability of current discharge limits to protect downstream environmental values.
C28	Water Reuse Mine affected water may be piped or trucked or transferred by some other means that does not contravene the conditions of this environmental authority and deposited either at German Creek Mine or into artificial water storage structures, such as farm dams or tanks, or used directly at properties owned by the environmental authority holder or a third party (with the written consent of the third party).

C29	Water general All determinations of water quality and biological monitoring must be: (a) Made in accordance with methods prescribed in the latest edition of the administering authority's (or its successor's) "<i>Monitoring and Sampling Manual</i>"; (b) Collected from the monitoring locations identified within this environmental authority, within 5 hours of each other where possible; (c) Carried out on representative samples; and (d) Analysed at a laboratory accredited (e.g. NATA) for the method of analysis being used. <i>Note: Condition C29 requires the Monitoring and Sampling Manual to be followed and where it is not followed because of exceptional circumstances this should be explained and reported with the results</i>
C30	The release of any contaminants as permitted by this environmental authority, directly or indirectly to waters, other than internal water management infrastructure that is installed and operated in accordance with a water management plan that complies with conditions C33 to C38 inclusive: (a) Must not produce any visible discolouration of receiving waters; and (b) Must not produce any slick or other visible or odorous evidence of oil, grease or petrochemicals nor contain visible floating oil, grease, scum, litter or other objectionable matter.
C31	Annual water monitoring reporting The following information must be recorded in relation to all water monitoring required under the conditions of this environmental authority and submitted to the administering authority in the specified format with each annual return: (a) The date on which the sample was taken; (b) The time at which the sample was taken; (c) The monitoring point at which the sample was taken; (d) The measured or estimated daily quantity of mine affected water released from all release points; (e) The release flow rate at the time of sampling for each release point; (f) The results of all monitoring and details of any exceedances of the conditions of this environmental authority; and (g) Water quality monitoring data must be provided to the administering authority in the specified electronic format upon request.
C32	Temporary interference with waterways Temporarily destroying native vegetation, excavating, or placing fill in a watercourse, lake or spring necessary for and associated with mining operations must be undertaken in accordance with the latest version of the Department Regional Development Manufacturing and Water's (or its successor's) Guideline – '<i>Riverine protection permit exemption requirements</i>' (WSS/2013/726).
C33	Water management plan A Water Management Plan must be developed by an appropriately qualified person and implemented for the duration of the mining activities. and reviewed at intervals no greater than 24 months.

C34	The Water Management Plan must: (a) Provide for effective management of actual and potential environmental impacts resulting from water management associated with the mining activity carried out under this environmental authority; and (b) Include: (i) A study of the source of contaminants; (ii) A water balance model for the site; (iii) A water management system for the site; (iv) Measures to manage and prevent saline drainage; (v) Measures to manage and prevent acid rock drainage; (vi) Contingency procedures for emergencies; and (vii) A program for monitoring and review of the effectiveness of the water management plan.
C35	The Water Management Plan must be reviewed each calendar year and the report must: (a) Include a statement that the Water Management Plan has been reviewed by an appropriately qualified person; and (b) Assess the plan against the requirements under condition C34; (c) Include recommended actions to ensure actual and potential environmental impacts are effectively managed for the coming year; and, (d) Identify any amendments made to the water management plan following the review.
C36	The holder of this environmental authority must attach to the review report required by condition C35, a written response to the report and recommended actions, detailing the actions taken or to be taken by the environmental authority holder on stated dates: (a) To ensure compliance with this environmental authority; and (b) To prevent a recurrence of any non-compliance issues identified.
C37	The review report required by condition C35 and the written response to the review report required by condition C36 must be submitted to the administering authority with the subsequent annual return under the signature of the appointed signatory for the annual return.
C38	Stormwater and water sediment controls An Erosion and Sediment Control Plan must be developed by an appropriately qualified person and implemented for all stages of the mining activities on the site to minimise erosion and the release of sediment to receiving waters and contamination of stormwater.

C39	The Erosion and Sediment Control Plan must demonstrate how erosion and sediment control measures detailed in the plan adequately minimise the release of sediment to receiving waters and must include at least the following: (a) An assessment of the size and characteristics of all catchment areas; and (b) An assessment of relevant properties of soils and waste materials; and (c) Identification of receiving waters environmental values, water quality objectives and management intent; and (d) Specification of minimum design criteria for erosion and sediment control structures for the catchment size and soil properties; and (e) Locations and descriptions of all erosion and sediment control measures; and (f) An audit schedule to ensure erosion and sediment control measures are maintained.
C40	The Erosion and Sediment Control Plan must be reviewed each calendar year. The review must be documented and must: (a) include a statement that the Erosion and Sediment Control Plan has been reviewed by an appropriately qualified person; and (b) assess the plan against the requirements of condition C39; and (c) include recommended actions to ensure actual and potential environmental impacts are effectively managed; and (d) provide details and timelines of the actions to be taken; and (e) identify any amendments made to the Erosion and Sediment Control Plan.
C41	Stormwater, other than mine affected water, is permitted to be released to waters from: (a) Erosion and sediment control structures that are installed and operated in accordance with the Erosion and Sediment Control Plan required by condition C38; and, (b) Water management infrastructure that is installed and operated, in accordance with a Water Management Plan that complies with conditions C33 to C38 inclusive, for the purpose of ensuring water does not become mine affected water
C42	The maintenance and cleaning of any vehicles, plant or equipment must not be carried out in areas from which contaminants can be released into any receiving waters.
C43	Any spillage of wastes, contaminants or other materials must be cleaned up as quickly as practicable to minimise the release of wastes, contaminants or materials to any stormwater drainage system or receiving waters.
C44	Sewage effluent All effluent released from the treatment plant must be monitored at the frequency and for the parameters specified in Table C9 Sewage effluent quality targets for dust suppression and irrigation.

Table C9 Sewage effluent quality targets for dust suppression and irrigation

Quality Characteristic	Release Limit	Limit type	Monitoring frequency
5-Day BOD	20 mg/L	Max	Fortnightly
Suspended Solids	39 mg/L	Max	Weekly
pH	6.5-8.0	Range	Daily and Weekly
Faecal Coliforms (organisms/100 mL)	150 thermotolerant coliforms/100 mL	Max	Monthly
Free Chlorine Residual	1 mg/L	Max	Daily and Weekly

RR1	Conditions C24 to C27 do not apply if the environmental authority holder is a participant of the FRREMP.
RR2	The environmental authority holder must notify the administering authority in a written statement within 20 business days of ceasing to be a participant of the FRREMP. The written statement must detail how the environmental authority holder is going to fulfil the requirements of conditions C24 to C27 .

Schedule D – Regulated Structures	
Condition No.	Condition
D1	Assessment of consequence category The consequence category of any structure must be assessed by a suitably qualified and experienced person in accordance with the latest version of the administering authority's <i>"Manual for assessing consequence categories and hydraulic performance of structures"</i> (ESR/2016/1933) at the following times: (a) Prior to the design and construction of the structure, if it is not an existing structure; or (b) Prior to any change in its purpose or the nature of its stored contents.
D2	A consequence assessment report and certification must be prepared for each structure assessed and the report may include a consequence assessment for more than one structure.
D3	Certification must be provided by the suitably qualified and experienced person who undertook the assessment, in the form set out in the <i>"Manual for assessing consequence categories and hydraulic performance of structures"</i> (ESR/2016/1933).
D4	Design and construction of a regulated structure Conditions D5 to D9 inclusive do not apply to existing structures.
D5	All regulated structures must be designed by, and constructed under the supervision of, a suitably qualified and experienced person in accordance with the requirements of the <i>"Manual for assessing consequence categories and hydraulic performance of structures"</i> (ESR/2016/1933).
D6	Construction of a regulated structure is prohibited unless: (a) The holder has submitted a consequence category assessment report and certification to the administering authority; (b) Certification for the design, design plan and the associated operating procedures has been certified by a suitably qualified and experienced person in compliance with the relevant condition of this authority.
D7	Certification must be provided by the suitably qualified and experienced person who oversees the preparation of the design plan in the form set out in the <i>"Manual for assessing consequence categories and hydraulic performance of structures"</i> (ESR/2016/1933), and must be recorded in the Register of Regulated Structures.

D8	Regulated structures must: (a) Be designed and constructed in compliance with the <i>“Manual for assessing consequence categories and hydraulic performance of structures”</i> (ESR/2016/1933); (b) Be designed and constructed with due consideration given to ensuring that the design integrity would not be compromised on account of: (i) Floodwaters entering the regulated dam from any watercourse or drainage line; and (ii) Wall failure due to erosion by floodwaters arising from any watercourse or drainage line. (c) For regulated structures associated with a failure to contain seepage, have the floor and sides of the dam designed and constructed to prevent or minimise the passage of the wetting front and any entrained contaminants through either the floor or sides of the dam during the operational life of the dam and for any period of decommissioning and rehabilitation of the dam.
D9	Certification by the suitably qualified and experienced person who supervises the construction must be submitted to the administering authority on the completion of construction of the regulated structure, and state that: (a) The 'as constructed' drawings and specifications meet the original intent of the design plan for that regulated structure; and (b) Construction of the regulated structure is in accordance with the design plan.
D10	Notification of affected persons All affected persons must be provided with a copy of the emergency action plan in place for each regulated structure: (a) For existing structures that are regulated structures, within 10 business days of this condition taking effect; (b) Prior to the operation of the new regulated structure; and (c) If the emergency action plan is amended, within 5 business days of it being amended.

D11	Operation of a regulated structure Operation of a regulated structure, except for an existing structure, is prohibited unless the holder has submitted to the administering authority in respect of regulated structure, all of the following: (a) One paper copy and one electronic copy of the design plan and certification of the 'design plan' in accordance with condition D6; (b) A set of 'as constructed' drawings and specifications; (c) Certification of the 'as constructed drawings and specifications' in accordance with condition D9; (d) Where the regulated structure is to be managed as part of an integrated containment system for the purpose of sharing the DSA volume across the system, a copy of the certified system design plan; (e) The requirements of this authority relating to the construction of the regulated structure have been met; (f) The holder has entered the details required under this authority, into a Register of Regulated Structures; and (g) There is a current operational plan for the regulated structure.
D12	For existing structures that are regulated structures: (a) Where the existing structure that is a regulated structure is to be managed as part of an integrated containment system for the purpose of sharing the DSA volume across the system, the holder must submit to the administering authority within 12 months of the commencement of this condition a copy of the certified system design plan including that structure; and (b) There must be a current operational plan for the existing structures.
D13	Each regulated structure must be maintained and operated, for the duration of its operational life until decommissioned and rehabilitated, in compliance with the current operational plan and, if applicable, the current design plan and associated certified 'as constructed' drawings.
D14	Mandatory reporting level (MRL) Conditions D15 to D16 inclusive only apply to Regulated Structures which have not been certified as low consequence category for 'failure to contain – overtopping'.
D15	The MRL must be marked on a regulated dam in such a way that during routine inspections of that dam, it is clearly observable.
D16	The holder must, as soon as practicable but within 48 hours of becoming aware, notify the administering authority when the level of the contents of a regulated dam reaches the MRL.
D17	The holder must, immediately on becoming aware that the MRL has been reached, act to prevent the occurrence of any unauthorised discharge from the regulated dam.
D18	The holder must record any changes to the MRL in the Register of Regulated Structures.
D19	Design storage allowance The holder must assess the performance of each regulated dam or linked containment system over the preceding November to May period based on actual observations of the available storage in each regulated dam or linked containment system taken prior to 1 July of each year.

D20	By 1 November of each year , storage capacity must be available in each regulated dam (or network of linked containment systems with a shared DSA volume), to meet the Design Storage Allowance (DSA) volume for the dam (or network of linked containment systems).
D21	The holder must, as soon as practicable but within 48 hours of becoming aware that the regulated dam (or network of linked containment systems) will not have the available storage to meet the DSA volume on 1 November of any year , notify the administering authority.
D22	The holder must, immediately on becoming aware that a regulated dam (or network of linked containment systems) will not have the available storage to meet the DSA volume on 1 November of any year , act to prevent the occurrence of any unauthorised discharge from the regulated dam or linked containment systems.
D23	Annual inspection report Each regulated structure must be inspected each calendar year by a suitably qualified and experienced person.
D24	At each annual inspection, the condition and adequacy of all components of the regulated structure must be assessed and a suitably qualified and experienced person must prepare an annual inspection report containing details of the assessment and include a recommendations section, with any recommended actions to ensure the integrity of the regulated structure or a positive statement that no recommendations are required.
D25	The suitably qualified and experienced person who prepared the annual inspection report must certify the report in accordance with the <i>“Manual for assessing consequence categories and hydraulic performance of structures”</i> (ESR/2016/1933).
D26	The holder must within 20 business days of receipt of the annual inspection report, provide to the administering authority: (a) The recommendations section of the annual inspection report; and (b) If applicable, any actions being taken in response to those recommendations; and (c) If, following receipt of the recommendations and (if applicable) recommended actions, the administering authority requests a copy of the annual inspection report from the holder, provide this to the administering authority within 10 business days of receipt of the request.
D27	The holder must provide a copy of any reports, documentation and certifications prepared under this authority, including but not limited to any Register of Regulated Structures, consequence assessment, design plan and other supporting documentation, to a new holder on transfer of this authority.
D28	Register of Regulated Structures A Register of Regulated Structures must be established and maintained by the holder for each regulated structure.
D29	The holder must provisionally enter the required information in the Register of Regulated Structures when a design plan for a regulated dam is submitted to the administering authority.
D30	The holder must make a final entry of the required information in the Register of Regulated Structures once compliance with condition D11 and D12 has been achieved.
D31	The holder must ensure that the information contained in the Register of Regulated Structures is current and complete on any given day.
D32	All entries in the Register of Regulated Structures must be approved by the chief executive officer for the holder of this authority, or their delegate, as being accurate and correct.

D33	The holder must, at the same time as providing the annual return, supply to the administering authority a copy of the records contained in the Register of Regulated Structures, in the electronic format required by the administering authority.
D34	Transitional arrangements All existing structures that have not been assessed in accordance with either the Manual or the former <i>“Manual for Assessing Hazard Categories and Hydraulic Performance”</i> (ESR/2016/1933) of Dams must be assessed and certified in accordance with the Manual prior to 13 April 2018.
D35	All existing structures must subsequently comply with the timetable for any further assessments in accordance with the Manual specified in Table D1 Transitional hydraulic performance requirements for existing structures , depending on the consequence category for each existing structure assessed in the most recent previous certification for that structure.
D36	Table D1 Transitional hydraulic performance requirements for existing structures ceases to apply for a structure once any of the following events has occurred: (a) It has been brought into compliance with the hydraulic performance criteria applicable to the structure under the Manual; or (b) It has been decommissioned; or (c) It has been certified as no longer being assessed as a regulated structure.
D37	Certification of the transitional assessment required by D34 and D35 (as applicable) must be provided to the administering authority prior to 30 March 2024 .

Table D1 Transitional hydraulic performance requirements for existing structures

Transition period required for existing structures to achieve the requirements of the Manual for Assessing Consequence Categories and Hydraulic Performance of Dams			
Compliance with criteria	High consequence	Significant consequence	Low consequence
>90% and a history of good compliance performance in last 5 years	No transition required	No transition required	No transitional conditions apply. Review consequence assessment every 7 years.
>70%-≤90%	13 September 2024 unless otherwise agreed with the administering authority, based on no history of unauthorised releases.	13 September 2027 unless otherwise agreed with the administering authority, based on no history of unauthorised releases.	No transitional conditions apply. Review consequence assessment every 7 years.
>50-≤70%	13 September 2022 unless otherwise agreed with the administering authority, based on no history of unauthorised releases.	13 September 2024 unless otherwise agreed with the administering authority, based on no history of unauthorised releases.	Review consequence assessment every 7 years.
≤50%	13 September 2022 or as per compliance requirements (e.g. TEP timing).	13 September 2022 or as per compliance requirements (e.g. TEP timing).	Review consequence assessment every 5 years.
Regulated levee designed to prevent the ingress of clean flood water <100% compliant.	13 September 2022 unless otherwise agreed with the administering authority.		
Note: Levees designed for the diversion of contaminated waters or protection of the structural integrity of a dam are not to be considered as part of this provision. These levees are considered a key design element of the relevant dam and transitional periods should as such align to that relevant compliance criteria and consequence category.			

Schedule E – Acoustic	
Condition No.	Condition
E1	Noise Nuisance Subject to condition E2 noise from the authorised mining activities must not exceed the levels specified in Table E1 Noise Limits, at any sensitive or commercial place
E2	When requested by the administering authority, noise monitoring must be undertaken within a reasonable and practicable timeframe nominated by the administering authority to investigate any complaint (which is neither frivolous nor vexatious nor based on mistaken believe in the opinion of the authorised officer) of environmental nuisance at any sensitive or commercial place, and the results must be notified within 14 days to the administering authority following completion of the monitoring.
E3	Monitoring and reporting All noise monitoring undertaken in accordance with condition E2 must be completed in accordance with the following noise monitoring requirements: (a) All noise monitoring must be conducted in accordance with the requirements of the most current version of the administering authority's Noise Measurement Manual (ESR/2016/2195), the relevant Australian Standard and the <i>Environmental Protection Regulation 2019</i> (Chapter 5, Part 4). (b) Source noise levels must be expressed as component noise levels for the purposes of comparison with noise limits. (c) All noise monitoring devices must be calibrated in accordance with AS IEC 61672.1-2004, or the most recent version of the Australian Standard. (d) Monitoring location(s) must be relevant to the matter(s) under investigation.
E4	If the administering authority's request for noise monitoring is in relation to a complaint and results exceed the limits in Table E1 Noise limits, then the environmental authority holder must: (a) Address the complaint including the use of appropriate dispute resolution if required; and (b) Implement noise abatement measures so that emissions of noise from the activity do not result in further environmental nuisance.
E5	Blasting must not cause the limits prescribed in Table E2 Blasting noise and vibration limits to be exceeded at a sensitive place or commercial place.

Table E1 – Noise limits

Noise level dB(A)	Monday to Saturday			Sunday and Public Holidays		
	7am – 6pm	6pm – 10pm	10pm – 7am	7am – 6pm	6pm – 10pm	10pm – 7am
	Noise measured at a sensitive place					
$L_{Aeq, adj, 1hr}^A$	35	35	35	35	35	35
L_{Amax}^B	-	-	50 ^B	-	-	50 ^B
Noise measured at a commercial place						
$L_{Aeq, adj, 1hr}$	35	35	35	35	35	35

NOTE - Associated notes and requirements:

A " $L_{Aeq, adj, 1hr}$ " means the equivalent continuous A-weighted sound pressure level, adjusted for noise character (tonal and or impulsive), measured in the presence of the noise under investigation over a time period of one (1) hour, using Fast response.

B " L_{Amax} ," means maximum instantaneous noise level during a noise measurement period. Up to 15 instantaneous events over the L_{Amax} are permitted over the monitoring period of 10pm to 7am.

Table E2 – Blasting noise and vibration limits

Blasting noise and vibration limits – surface mining	Sensitive place and commercial place criteria	
	7am to 6pm	6pm to 7am
Airblast overpressure	115dB (Linear) Peak for 4 out of 5 consecutive blasts initiated and not greater than 120 dB (Linear) Peak at any time	0dB (no blasting)
Ground vibration peak particle velocity	5mm/second peak particle velocity for 9 out of 10 consecutive blasts and not greater than 10 mm/second peak particle velocity at any time	0dB (no blasting)

Schedule F – Waste Management	
Condition No.	Condition
F1	Unless otherwise authorised by the conditions of this environmental authority, all waste generated in carrying out the activity must be lawfully reused, recycled or removed to a facility that can lawfully accept the waste.
F2	A designated area must be set aside for the segregation of economically viable, recyclable solid and liquid waste.
F3	Storage of Tyres Tyres stored awaiting disposal or transport for take-back and, recycling, or waste-to-energy options should be stockpiled in volumes less than 3m in height and 200m² in area and at least 10m from any other tyre storage area.
F4	All reasonable and practicable fire prevention measures must be implemented, including removal of grass and other materials within a 10m radius of the scrap tyre storage area.
F5	Waste Management Plan A Waste management Plan must: (a) Be developed by an appropriately qualified person; (b) Implemented for the duration of the mining activities, and (c) Include all the following: (i) A description of the activities that generate waste; (ii) A procedure for recording the types and amounts of wastes generated, (iii) A survey record of the size and location (using coordinates) of all described waste disposal areas on site ; (iv) Provisions for the management of any leachates; (v) The characteristics of the wastes generated; (vi) How the waste and resource management hierarchy will be implemented for each waste type (i.e. avoidance, reuse, recycling, energy recovery, disposal); (vii) How the waste will be stored, handled and transferred in a proper and effective manner; (viii) Procedures for managing accidents, spills, and other incidents associated with the receipt, storage, transport, and disposal of waste; (ix) Indicators or other criteria on which the performance of the waste management plan will be assessed; (x) A program of periodic review to ensure the plan meets the requirements of this environmental authority; and (xi) Staff training and induction to the waste management program.

Schedule G – Land	
Condition No.	Condition
G1	No net loss of remnant vegetation as the result of the commissioning of roads and infrastructure within the Lake Lindsay mining lease shall occur.
G2	Records of all disturbance of all remnant vegetation, including vegetation type, as a result of the commissioning of roads and infrastructure within the Lake Lindsay mining lease must be recorded.
G3	A plan nominating the areas to achieve the commitment of no net loss of remnant vegetation as a result of the commissioning of roads and infrastructure within the Lake Lindsay mining lease must be maintained and kept for the life of the environmental authority.
G4	Topsoil and capping material The holder of this environmental authority must maintain an up to date record of the topsoil and capping requirements for rehabilitation of the mine and the availability of suitable topsoil and capping material on site must be detailed in the estimated rehabilitation cost application.

Schedule H – Groundwater	
Condition No.	Condition
H1	Contaminants from the activity must not be released to groundwater.
H2	Bore Construction, Maintenance and Decommissioning The construction, maintenance and management of groundwater bores must be undertaken in a manner that prevents or minimises impacts to the environment and ensures the integrity of bores to obtain accurate monitoring.
H3	A bore report must be kept for each monitoring bore which includes: (a) A unique identification reference number and geographic coordinate location; and (b) Construction information including but not limited to the depth of bore, depth and length of casing, depth and length of screening and bore sealing details; and (c) Stratigraphy and target hydrogeological unit of the bore; and (d) Depth at which groundwater was intercepted and the final standing water level (SWL) after bore development.
H4	Groundwater Monitoring and Management Program On or before 1 June 2024 a Groundwater Monitoring and Management Program (GMMP) must be developed and implemented by the environmental authority holder for all mining activities.
H5	The GMMP required by condition H4 must: (a) Provide a hydrogeological conceptual groundwater model in accordance with the most recent version of the <i>Australian Groundwater Modelling Guidelines</i> (2012); (b) Include all hydrogeological units potentially impacted by the activities authorised under this environmental authority; (c) Identify all potential sources of contamination to groundwater from the activities; and (d) Identify all environmental values that may be impacted; and (e) Describe the groundwater monitoring and data analysis that will be undertaken to achieve the following objectives: (i) Detect impacts to groundwater quality and standing water level (SWL) due to the activities authorised under this environmental authority; and (ii) Determine trends in groundwater quality and SWL; and (f) Document groundwater management and monitoring methodologies undertaken for the duration of all the activities authorised under this environmental authority; and (g) Provide an appropriate quality assurance and quality control program; and (h) Include a review process to identify improvements to the program that includes addressing any comments provided by the administering authority.

H6	A review report for the GMMP required by condition H4 must be produced by 30 June 2026 and every 2 subsequent years and include: (a) An analysis of the all the groundwater quality and SWL monitoring data for all groundwater bores listed within Table H1 Groundwater monitoring locations and frequency; (b) An assessment of groundwater quality and SWL trends for all monitoring data from all groundwater bores listed in Table H1 Groundwater monitoring locations and frequency; (c) An assessment of the adequacy of the conceptual groundwater model to accurately determine contaminant transport and changes to SWL; (d) An assessment of any impacts on groundwater quality and SWL due to the mining activities; (e) An assessment of any interactions with, or impacts to, surface water resulting from changes to groundwater quality and SWL due to the mining activities; (f) Recommendations, if any, for the environmental authority holder to complete to address any inadequacy or impacts identified by (a) through (e) of this condition.
H7	Within 28 days of producing or receiving the review report under condition H6, the environmental authority holder must provide to the administering authority: (a) The review report; (b) If applicable, any actions being taken by the environmental authority holder to address the recommendations of the review report; and (c) If action is not being taken to address a recommendation, the environmental authority holder must provide justification for not taking action.
H8	By 30 June 2026, the environmental authority holder must submit a report to the administering authority that proposes groundwater monitoring locations details to populate Table H1 Groundwater monitoring locations and frequency, and Table H3 Groundwater standing water level trigger threshold.
H9	By 10 December 2026, the environmental authority holder must submit a report to the administering authority. The report must: (a) Propose groundwater quality trigger levels to populate Table H2 Groundwater quality triggers based on a minimum of 12 sampling events per bore; and (b) Propose groundwater SWL triggers to replace all 'TBD's in Table H3 Groundwater standing water level trigger threshold based on a minimum of 12 measurements per bore. <i>Note: The report required by this condition must consider the requirements of the administering authority's, or its successor's, most recent edition of the Guideline: "Using monitoring data to assess groundwater quality and potential environmental impacts" (DES, 2021).</i>
H10	Groundwater monitoring Groundwater must be monitored at the location and frequencies defined in Table H1 Groundwater monitoring locations and frequency for the quality characteristics specified in in Table H2 Groundwater quality triggers and SWLs stated in Table H3 Groundwater standing water level trigger threshold.
H11	Monitoring results from groundwater bores identified in Table H1 Groundwater monitoring locations and frequency must not exceed any of the trigger levels stated in Table H2 Groundwater quality triggers on 3 consecutive monitoring occasions.

H12	Exceedance investigation - groundwater quality If monitoring undertaken in accordance with condition H11 shows exceedance of quality triggers in Table H2 Groundwater quality triggers on 3 consecutive monitoring occasions, the holder of this environmental authority, after receiving results, must: (a) Notify the administering authority via WaTERS within 24 hours; (b) complete an investigation within 14 days to determine if the exceedance is result of mining activities; (c) Provide a report of the investigation to the administering authority via WaTERS within 14 days of completion of the investigation; and (d) If the investigation determines that the mining activities are a potential cause or contributor to the exceedance, then: (i) Determine whether environmental harm has occurred; (ii) Any action required to mitigate the environmental harm; and (iii) Submit the water quality results to the administering authority via WaTERS.
H13	Monitoring results from groundwater bores identified in Table H1 Groundwater monitoring locations and frequency must not exceed any of SWL trigger levels stated in Table H3 Groundwater standing water level trigger threshold.
H14	Exceedance investigation- SWL If monitoring undertaken in accordance with condition H13 shows exceedance of the thresholds in Table H3 Groundwater standing water level trigger threshold, the holder of this environmental authority, after receiving results must: (a) Notify the administering authority via WaTERS within 24 hours; (b) Complete an investigation into the cause of the exceedance within 10 business days; (c) If the investigation determines that the mining activities are a potential cause or contributor to the exceedance-- (i) Notify the administering authority via WaTERS within 24 hours of making the determination; (ii) Identify any impacts to environmental values and/or water users as a result of the exceedance; and (iii) Take immediate actions to mitigate any identified impacts and notify the administering authority of when action has been completed.
H15	Monitoring and sampling must be carried out in accordance with the requirements of the latest version of the following documents unless otherwise approved by the administering authority: (a) <i>Monitoring and Sampling Manual: Environmental Protection (Water) Policy</i>, Department of Environment and Science, 2018; (b) <i>Groundwater Sampling and Analysis – A Field Guide</i>, (2009:27 GeoCat#6890.1); and (c) Australian Standard AS/NZS 5667.11:1998 Water quality—Sampling -Part 11: Guidance on sampling of groundwaters.

H16	The groundwater quality and SWL data of all groundwater bores listed within Table H1 Groundwater monitoring locations must be submitted annually on 1 July to the administering authority via WaTERS.
------------	---

Table H1 Groundwater monitoring locations and frequency

Monitoring Bore	Hydrogeological Unit	Location (GDA2020)		Surface RL (mAHD) ¹	Monitoring Frequency ²	Parameters
		Latitude	Longitude			
<i>e.g., MB1</i>	<i>e.g., Alluvium</i>			<i>TBD</i>	Quarterly	Water Quality and Water Level

Table H1 Notes:

1. RL (relative level) must be measured to the nearest 5cm (where a monitoring bore is installed it is measured from the top of the bore casing).
2. The initial frequency of monitoring for alluvial bores will involve more frequent sampling than quarterly to meet the 12 sampling event requirements of condition **H8**.

Table H2 Groundwater quality triggers

Parameter*	Units	Hydrogeological Unit - Trigger Levels		
		TBD	TBD	TBD
Physico-chemical parameters/sulfate				
pH	pH Units	TBD		
Electrical Conductivity (EC)	µS/cm	TBD		
Sulfate	mg/L	TBD		
Total Dissolved Solids	mg/L	TBD		
Major Ions				
Calcium	mg/L	TBD		
Magnesium	mg/L	TBD		
Sodium	mg/L	TBD		
Potassium	mg/L	TBD		
Chloride	mg/L	TBD		
Sulfate	mg/L	TBD		
Carbonate	mg/L	TBD		
Bicarbonate	mg/L	TBD		
Phosphate	mg/L	TBD		
Nitrate	mg/L	TBD		
Ammonium	mg/L	TBD		
Fluoride	mg/L	TBD		
Metals/metalloids (Dissolved)				
Iron	µg/L	TBD		
Aluminium	µg/L	TBD		
Silver	µg/L	TBD		
Arsenic	µg/L	TBD		
Mercury	µg/L	TBD		
Antimony	µg/L	TBD		
Cobalt	µg/L	TBD		
Nickel	µg/L	TBD		
Zinc	µg/L	TBD		
Cadmium	µg/L	TBD		
Chromium	µg/L	TBD		
Copper	µg/L	TBD		
Lead	µg/L	TBD		
Boron	µg/L	TBD		
Manganese	µg/L	TBD		
Molybdenum	µg/L	TBD		
Selenium	µg/L	TBD		
Vanadium	µg/L	TBD		
Uranium	µg/L	TBD		
Petroleum Hydrocarbons (C6-C9)	µg/L	TBD		
Petroleum hydrocarbons (C10-C36)	µg/L	TBD		

*Parameters are subject to review and change based on findings of the GMMP required by condition H4.

Table H3 Groundwater standing water level trigger threshold

Monitoring location	Hydrogeological Unit	Baseline water level (mAHD)	Standing Water Level Trigger Threshold (mAHD)
e.g., MB01	e.g., Alluvium	TBD	TBD

Schedule I – Biodiversity	
Condition No.	Condition
I1	Prescribed environmental matters – Matters of State Environmental Significance Impacts to Matters of State Environmental Significance (MSES), as a result of carrying out the activity on ML700076 must only occur within the locations and to the maximum extents stated in Table I1 Authorised residual impacts to prescribed environmental matters.
I2	All impacts to MSES must be determined, documented, and mapped by an appropriately qualified person.
I3	Records of impacts to MSES in condition I2 must be kept for the life of the environmental authority and include: (a) The size and extent of impact; and (b) Details about the condition of the MSES (e.g. dominant vegetation and remnant status); and (c) A determination of whether the impact is a significant residual impact.
I4	Environmental Offsets An environmental offset must be made in accordance with the <i>Environmental Offsets Act 2014</i> and <i>Queensland Environmental Offsets Policy</i>, Version 1.14, effective 30 June 2023, for the maximum extent of impact to each MSES for which an environmental offset is required as listed in Table I1 Authorised residual impacts to prescribed environmental matters. <i>Note: Deemed conditions provided in section 16 of the Environmental Offsets Act 2014 also apply to this authority. Any contravention of a deemed condition will be dealt with under the Environmental Protection Act 1994.</i>

Table I1 Authorised residual impacts to prescribed environmental matters (ML700076)

Prescribed Environmental Matter	Maximum Extent of Impact (ha)	Location	Environmental Offset Required (Yes/No)
Connectivity Areas			
<i>Least concern RE within a defined distance of a watercourse – 11.5.3</i>	12.06	Refer to Appendix 3, Figure 3.1	Yes
Protected Wildlife Habitat			
<i>Habitat for an animal that is endangered wildlife – Koala</i>	17	Refer to Appendix 3, Figure 3.1	No
<i>Habitat for an animal that is vulnerable wildlife – Squatter pigeon</i>	17	Refer to Appendix 3, Figure 3.1	No
<i>Habitat for an animal that is vulnerable wildlife – Ornamental snake</i>	6.27	Refer to Appendix 3, Figure 3.1	No
<i>Habitat for an animal that is special least concern wildlife – Echidna</i>	70	Refer to Appendix 3, Figure 3.2	No

Definitions

Key terms and/or phrases used in this document are defined in this section. Where a term is not defined, the definition in the *Environmental Protection Act 1994*, its regulations or environmental protection policies must be used. If a word remains undefined it has its ordinary meaning.

Acceptance criteria means the measures by which the actions implemented to rehabilitate the land are deemed to be complete. The acceptance criteria indicate the success of the rehabilitation outcome or remediation of areas which have been significantly disturbed by the mining activities. Acceptance criteria may include information regarding:

- (a) Vegetation establishment, survival and succession;
- (b) Vegetation productivity, sustained growth and structure development;
- (c) Fauna colonisation and habitat development;
- (d) Ecosystem processes such as soil development and nutrient cycling, and the recolonisation of specific fauna groups such as collembola, mites and termites which are involved in these processes;
- (e) Microbiological studies including recolonisation by mycorrhizal fungi, microbial biomass and respiration;
- (f) Effects of various establishment treatments such as deep ripping, topsoil handling, seeding and fertiliser application on vegetation growth and development;
- (g) Resilience of vegetation to disease, insect attack, drought and fire; and
- (h) Vegetation water use and effects on ground water levels and catchment yields.

Acid rock drainage or **acid mine drainage** means any contaminated discharge emanating from a mining activity formed through a series of chemical and biological reactions when geological strata is disturbed and exposed to oxygen and moisture as a result of mining activities.

Administering authority is the agency or department that administers the environmental authority provisions under the *Environmental Protection Act 1994*.

Affected person is someone whose drinking water can potentially be impacted as a result of discharges from a dam or their life or property can be put at risk due to dwellings or workplaces being in the path of a dam break flood.

Airblast overpressure means energy transmitted from the blast site within the atmosphere in the form of pressure waves. The maximum excess pressure in this wave, above ambient pressure is the peak airblast overpressure measured in decibels linear (dBL).

Annual exceedance probability or AEP means the probability that at least one event in excess of a particular magnitude will occur in any given year.

Annual inspection report means an assessment prepared by a suitably qualified and experienced person containing details of the assessment against the most recent consequence assessment report and design plan (or system design plan);

- (a) Against recommendations contained in previous annual inspections reports;
- (b) Against recognised dam safety deficiency indicators;
- (c) For changes in circumstances potentially leading to a change in consequence category;
- (d) For conformance with the conditions of this authority;
- (e) For conformance with the 'as constructed' drawings;
- (f) For the adequacy of the available storage in each regulated dam, based on an actual observation or observations taken after 31 May each year but prior to 1 November of that year of accumulated sediment, state of the containment barrier and the level of liquids in the **dam** (or network of linked containment systems);

(g) For evidence of conformance with the current operational plan.

ANZECC means the Australian and New Zealand Guidelines for Fresh Marine Water Quality 2000.

Appropriately qualified person means a person who has professional qualifications, training, skills or experience relevant to the nominated subject matter and can give authoritative assessment, advice and analysis on performance relative to the subject matter using the relevant protocols, standards, methods or literature.

Assessed or **assessment** by a suitably qualified and experienced person in relation to a consequence assessment of a dam, means that a statutory declaration has been made by that person and, when taken together with any attached or appended documents referenced in that declaration, all of the following aspects are addressed and are sufficient to allow an independent audit at any time:

- (a) Exactly what has been assessed and the precise nature of that assessment;
- (b) The relevant legislative, regulatory and technical criteria on which the assessment has been based;
- (c) The relevant data and facts on which the assessment has been based, the source of that material, and the efforts made to obtain all relevant data and facts; and
- (d) The reasoning on which the assessment has been based using the relevant data and facts, and the relevant criteria.

Associated works in relation to a dam, means:

- (a) Operations of any kind and all things constructed, erected or installed for that dam; and
- (b) Any land used for those operations.

Authority means environmental authority or a development approval.

Background means with reference to the water schedule, means the average of samples taken prior to the commencement of mining from the same waterway that the current sample has been taken.

Bed and banks means for a waters, river, creek, stream, lake, lagoon, pond, swamp, wetland or dam means land over which the water of the waters, lake, lagoon, pond, swamp, wetland or dam normally flows or that is normally covered by the water, whether permanently or intermittently; but does not include land adjoining or adjacent to the bed and banks that is from time to time covered by floodwater.

Blasting means the use of explosive materials to fracture:

- (a) Rock, coal and other minerals for later recovery, or
- (b) Structural components or other items to facilitate removal from a site or for reuse

Certification means assessment and approval must be undertaken by a suitably qualified and experienced person in relation to any assessment or documentation required by this Manual, including design plans, 'as constructed' drawings and specifications, construction, operation or an annual report regarding regulated structures, undertaken in accordance with the Board of Professional Engineers of Queensland Policy Certification by RPEQs (ID: 1.4 (2A)).

Certifying, certify or certified have a corresponding meaning to certification.

Chemical means –

- (a) An agricultural chemical product or veterinary chemical product within the meaning of the *Agricultural and Veterinary Chemicals Code Act 1994* (Commonwealth); or
- (b) A dangerous good under the dangerous goods code; or
- (c) A lead hazardous substance within the meaning of the *Workplace Health and Safety Regulation 2008*; or
- (d) A drug or poison in the Standard for the Uniform Scheduling of Drugs and Poisons prepared by the Australian Health Ministers' Advisory Council and published by the Commonwealth; or

(e) Any substance used as, or intended for use as –

- (i) A pesticide, insecticide, fungicide, herbicide, rodenticide, nematocide, miticide, fumigant or related product; or
- (ii) A surface active agent, including, for example, soap or related detergent; or
- (iii) A paint solvent, pigment, dye, printing ink, industrial polish, adhesive, sealant, food additive, bleach, sanitiser, disinfectant, or biocide; or
- (iv) A fertiliser for agricultural, horticultural or garden use; or

(f) A substance used for, or intended for use for –

- (i) Mineral processing or treatment of metal, pulp and paper, textile, timber, water or wastewater; or
- (ii) Manufacture of plastic or synthetic rubber.

Commercial place means a work place used as an office or for business or commercial purposes, which is not part of the mining activity and does not include employees accommodation or public roads.

Construction or **constructed** in relation to a regulated structure includes building a new structure and lifting or otherwise modifying an existing structure, but does not include investigations and testing necessary for the purpose of preparing a design plan.

Consequence in relation to a structure as defined, means the potential for environmental harm resulting from the collapse or failure of the structure to perform its primary purpose of containing, diverting or controlling flowable substances.

Consequence category means a category, either low, significant or high, into which a structure is assessed as a result of the application of tables and other criteria in the *Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933)*.

Dam means a land-based structure or a void that contains, diverts or controls flowable substances, and includes any substances that are thereby contained, diverted or controlled by that land-based structure or void and **associated works**.

Design plan is a document setting out how all identified consequence scenarios are addressed in the planned design and operation of a regulated structure.

Design storage allowance or **DSA** means an available volume, estimated in accordance with the *Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933)* published by the administering authority, must be provided in a dam as at 1 November each year in order to prevent a discharge from that dam to an **annual exceedance probability (AEP)** specified in that Manual.

Disturbance of land includes:

- (a) Compacting, removing, covering, exposing or stockpiling of earth
- (b) Removal or destruction of vegetation or topsoil or both to an extent where the land has been made susceptible to erosion
- (c) Carrying out mining within a watercourse, waterway, wetland or lake
- (d) The submersion of areas by tailings or hazardous contaminant storage and dam/structure walls
- (e) Temporary infrastructure, including any infrastructure (roads, tracks, bridges, culverts, dam/structures, bores, buildings, fixed machinery, hardstand areas, airstrips, helipads etc) which is to be removed after the mining activity has ceased
- (f) Releasing of contaminants into the soil, or underlying geological strata.

However, the following areas are not included when calculating areas of 'disturbance':

- (a) Areas off lease (e.g. roads or tracks which provide access to the mining lease)
- (b) Areas previously disturbed which have achieved the rehabilitation outcomes
- (c) By agreement with the administering authority, areas previously disturbed which have not achieved the rehabilitation objective(s) due to circumstances beyond the control of the mine operator (such as climatic conditions)
- (d) Areas under permanent infrastructure. Permanent infrastructure includes any infrastructure (roads, tracks, bridges, culverts, dam/structures, bores, buildings, fixed machinery, hardstand areas, airstrips, helipads etc) which is to be left by agreement with the landowner
- (e) Disturbance that pre-existed the grant of the tenure.

EC means electrical conductivity.

Effluent means treated waste water discharged from sewage treatment plants.

Emergency action plan means documentation forming part of the operational plan held by the holder or a nominated responsible officer, which identifies emergency conditions that sets out procedures and actions that will be followed and taken by the dam owner and operating personnel in the event of an emergency. The actions are to minimise the risk and consequences of failure, and ensure timely warning to affected persons and the implementation of protection measures. The plan must require dam owners to annually review and update contact information where required.

Environmental offset has the meaning in section 7 of the *Environmental Offsets Act 2014*.

Existing structure means a structure that prior to 13 September 2017 meets any or both of the following, a structure:

- (a) With a design that is in accordance with the Manual for Assessing Consequence Categories and Hydraulic Performance of Structures (ESR/2016/1933, version 5.00) and that is considerably in progress;
- (b) That is under considerable construction or that is constructed.

Floodwater means water overflowing, or that has overflowed, from waters, river, creek, stream, lake, pond, wetland or dam onto or over riparian land that is not submerged when the watercourse or lake flows between or is contained within its bed and banks.

Flowable substance means matter or a mixture of materials which can flow under any conditions potentially affecting that substance. Constituents of a flowable substance can include water, other liquids fluids or solids, or a mixture that includes water and any other liquids, fluids or solids either in solution or suspension.

FRREMP means a Fitzroy Basin Receiving Environment Monitoring Program for the region in which the EA is located, that has been endorsed in writing by the administering authority.

German Creek Mine means the activities authorised under environmental authority EPML00732613.

Holder for a mining tenement, means a holder of the tenement under the *Mineral Resources Act 1989*, and the holder of the associated environmental authority under the *Environmental Protection Act 1994*.

Hydraulic performance means the capacity of a regulated dam to contain or safely pass flowable substances based on the design criteria specified for the relevant consequence category in the Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933).

Hydrogeological unit is any soil or rock unit or zone that by virtue of its hydraulic properties has a distinct influence on the storage or movement of groundwater.

Infrastructure means water storage dams, levees, roads and tracks, buildings and other structures built for the purpose of the mining activity.

Land in the 'land schedule' of this document means land excluding waters and the atmosphere, that is, the term has a different meaning from the term as defined in the *Environmental Protection Act 1994*. For the purposes of the *Acts Interpretation Act 1954*, it is expressly noted that the term 'land' in this environmental authority relates to physical land and not to interests in land.

Land capability as defined in the DME 1995 Technical Guidelines for the Environmental Management of Exploration and Mining in Queensland.

Land use means the selected post mining use of the land, which is planned to occur after the cessation of mining operations.

Levee means an embankment that only provides for the containment and diversion of stormwater or flood flows from a contributing catchment, or containment and diversion of flowable materials resulting from releases from other works, during the progress of those stormwater or flood flows or those releases; and does not store any significant volume of **water** or **flowable substances** at any other times.

Limit of reporting or LOR means typical reporting for method stated. ICPMS/CV FIMS – analytical method required to achieve LOR.

m means metres.

Matters of State Environmental Significance has its meaning under the *Environmental Offsets Regulation 2014*.

Mandatory reporting level or MRL means a warning and reporting level determined in accordance with the criteria in the Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933) published by the administering authority.

Manual means the Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933) published by the administering authority, as amended from time to time.

Maximum extent of impact means the total, cumulative, residual extent and duration of impact to a prescribed environmental matter that will occur over a project's life after all reasonable avoidance and reasonable on-site mitigation measures have been, or will be, undertaken.

mg/L means milligrams per litre.

Mine affected water:

- (a) Means the following types of water:
 - (i) Pit water, tailings dam water, processing plant water
 - (ii) Water contaminated by a mining activity which would have been an environmentally relevant activity under Schedule 2 of the *Environmental Protection Regulation 2008* if it had not formed part of the mining activity
 - (iii) Rainfall runoff which has been in contact with any areas disturbed by mining activities which have not yet been rehabilitated, excluding rainfall runoff discharging through release points associated with erosion and sediment control structures that have been installed in accordance with the standards and requirements of an Erosion and Sediment Control Plan to manage such runoff, provided that this water has not been mixed with pit water, tailings dam water, processing plant water or workshop water
 - (iv) Groundwater which has been in contact with any areas disturbed by mining activities which have not yet been rehabilitated;
 - (v) Groundwater from the mine's dewatering activities
 - (vi) A mix of mine affected water (under any of paragraphs i)-v) and other water.
- (b) Does not include surface water runoff which, to the extent that it has been in contact with areas disturbed by mining activities that have not yet been completely rehabilitated, has only been in contact with:

- (i) Land that has been rehabilitated to a stable landform and either capped or revegetated in accordance with the acceptance criteria set out in the environmental authority but only still awaiting maintenance and monitoring of the rehabilitation over a specified period of time to demonstrate rehabilitation success, or
- (ii) Land that has partially been rehabilitated and monitoring demonstrates the relevant part of the landform with which the water has been in contact does not cause environmental harm to waters or groundwater, for example:
 - (1) Areas that are been capped and have monitoring data demonstrating hazardous material adequately contained with the site
 - (2) Evidence provided through monitoring that the relevant surface water would have met the water quality parameters for mine affected water release limits in this environmental authority, if those parameters had been applicable to the surface water runoff, or
- (iii) Both

Modification or modifying (see definition of 'construction')

NATA means National Association of Testing Authorities, Australia

Natural flow means the flow of water through waters caused by nature.

Non polluting means having no adverse impacts upon the receiving environment.

Operational plan includes:

- (a) Normal operating procedures and rules (including clear documentation and definition of process inputs in the DSA);
- (b) Contingency and emergency action plans including operating procedures designed to avoid and/or minimise environmental impacts including threats to human life resulting from any overtopping or loss of structural integrity of the regulated structure.

Participant of the FRREMP means an environmental authority holder that is identified as a current participant by the organisation carrying out the Regional REMP.

Peak particle velocity or **ppv** means a measure of ground vibration magnitude which is the maximum rate of change of ground displacement with time, usually measured in millimetres/second (mm/s). **protected area** means:

- (a) A protected area under the *Nature Conservation Act 1992*;
- (b) A marine park under the *Marine Parks Act 2004*; or
- (c) A World Heritage Area.

Progressive rehabilitation means rehabilitation (defined below) undertaken progressively or a staged approach to rehabilitation as mining operations are ongoing.

Receiving environment means all groundwater, surface water, land and sediments that are not disturbed areas authorised by this environmental authority.

Receiving waters means all groundwater and surface water that are not disturbed areas authorised by this environmental authority.

Reference site (or analogue site) may reflect the original location, adjacent area or another area where rehabilitation success has been completed for a similar biodiversity. Details of the reference site may be presented as photographs, computer generated images and vegetation models etc.

Register of regulated structures includes:

- (a) Date of entry in the register;
- (b) Name of the structure, its purpose and intended/actual contents;
- (c) The consequence category of the dam as assessed using the Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933);
- (d) Dates, names, and reference for the design plan plus dates, names, and reference numbers of all document(s) lodged as part of a design plan for the dam;
- (e) Name and qualifications of the suitably qualified and experienced person who certified the design plan and 'as constructed' drawings;
- (f) For the regulated dam, other than in relation to any levees –
 - (i) The dimensions (metres) and surface area (hectares) of the dam measured at the footprint of the dam;
 - (ii) Coordinates (latitude and longitude in GDA94) within five metres at any point from the outside of the dam including its storage area
 - (iii) Dam crest volume (megalitres);
 - (iv) Spillway crest level (metres AHD);
 - (v) Maximum operating level (metres AHD);
 - (vi) Storage rating table of stored volume versus level (metres AHD);
 - (vii) Design storage allowance (megalitres) and associated level of the dam (metres AHD);
 - (viii) Mandatory reporting level (metres AHD);
- (g) The design plan title and reference relevant to the dam;
- (h) The date construction was certified as compliant with the design plan;
- (i) The name and details of the suitably qualified and experienced person who certified that the constructed dam was compliant with the design plan;
- (j) Details of the composition and construction of any liner;
- (k) The system for the detection of any leakage through the floor and sides of the dam;
- (l) Dates when the regulated dam underwent an annual inspection for structural and operational adequacy, and to ascertain the available storage volume for 1 November of any year;
- (m) Dates when recommendations and actions arising from the annual inspection were provided to the administering authority;
- (n) Dam water quality as obtained from any monitoring required under this authority as at 1 November of each year.

Regulated structure means any structure in the significant or high consequence category as assessed using the *Manual for assessing consequence categories and hydraulic performance of structures (ESR/2016/1933)* published by the administering authority. A regulated structure does not include:

- (a) A fabricated or manufactured tank or container, designed and constructed to an Australian Standard that deals with strength and structural integrity of that tank or container;
- (b) A sump or earthen pit used to store residual drilling material and drilling fluid only for the duration of drilling and well completion activities;
- (c) A flare pit.

Rehabilitation means the process of reshaping and revegetating land to restore it to a stable landform and in accordance with the acceptance criteria set out in this environmental authority and, where relevant, includes remediation of contaminated land.

Release influence period is the period during which the downstream monitoring points are influenced by mine affected water releases and includes both the duration of release and any lag time between release point/s and the corresponding downstream monitoring points.

Representative means a sample set which covers the variance in monitoring or other data either due to natural changes or operational phases of the mining activities.

Residual void means an open pit resulting from the removal of ore and/or waste rock which will remain following the cessation of all mining activities and completion of rehabilitation processes.

Saline drainage means the movement of waters, contaminated with salt(s), as a result of the mining activity.

Self sustaining means an area of land which has been rehabilitated and has maintained the required acceptance criteria without human intervention for a period nominated by the administering authority.

Sensitive place means:

- (a) A dwelling, residential allotment, mobile home or caravan park, residential marina or other residential premises; or
- (b) A motel, hotel or hostel; or
- (c) An educational institution; or
- (d) A medical centre or hospital; or
- (e) A protected area under the *Nature Conservation Act 1992*, the *Marine Parks Act 2004* or a World Heritage Area; or
- (f) A public park or gardens.

Note: The definition of 'sensitive place' and 'commercial place' is based on Schedule 1 of EPP Noise. That is, a sensitive place is inside or outside on a dwelling, library and educational institution, childcare or kindergarten, school or playground, hospital, surgery or other medical institution, commercial & retail activity, protected area or an area identified under a conservation plan under Nature Conservation Act 1992 as a critical habitat or an area of major interest, marine park under Marine Parks Act 2004, park or garden that is outside of the mining lease and open to the public for the use other than for sport or organised entertainment. A commercial place is inside or outside a commercial or retail activity.

A mining camp (i.e., accommodation and ancillary facilities for mine employees or contractors or both, associated with the mine the subject of the environmental authority) is not a sensitive place for that mine or mining project, whether or not the mining camp is located within a mining tenement that is part of the mining project the subject of the environmental authority. For example, the mining camp might be located on neighbouring land owned or leased by the same company as one of the holders of the environmental authority for the mining project, or a related company. Accommodation for mine employees or contractors is not a sensitive place if the land is held by a mining company or related company, and if occupation is restricted to the employees, contractors and their families for the particular mine or mines which are held by the same company or a related company.

However, a township (occupied by the mine employees, contractors and their families for multiple mines that are held by different companies) would be a sensitive place, even if part or all of the township is constructed on land owned by one or more of the companies.

Slightly moderately disturbed or SMD means slightly moderately disturbed level of protection guideline refers ANZECC & ARMCANZ (2000).

Spillway means a weir, channel, conduit, tunnel, gate or other structure designed to permit discharges from the dam, normally under flood conditions or in anticipation of flood conditions.

Stable in relation to land, means landform dimensions are or will be stable within tolerable limits now and in the foreseeable future. Stability includes consideration of geotechnical stability, settlement and consolidation allowances,

bearing capacity (trafficability), erosion resistance and geochemical stability with respect to seepage, leachate and related contaminant generation.

Surface disturbance is any disturbance of the land but does not include the excavation of a pit for open cut mining or subsidence associated with underground mining.

Sub-surface disturbance is excavation of a pit for open cut mining and can include any other type of surface disturbance.

Stormwater means all surface water runoff from rainfall.

Suitably qualified and experienced person means a person who is a Registered Professional Engineer of Queensland under the provisions of the *Professional Engineers Act 2002*, who has an **appropriate level of expertise** in the structures, geomechanics, hydrology, hydraulics and environmental impact of watercourse diversions.

An **appropriate level of expertise** includes:

- (a) Demonstrable competency, experience and expertise in:
 - (i) Investigation, design or construction of watercourses diversions
 - (ii) Operation and maintenance of watercourse diversions
 - (iii) Geomechanics with particular emphasis on channel equilibrium, geology and geochemistry
 - (iv) Hydrology with particular reference to flooding, estimation of extreme storms, water management or meteorology
 - (v) Hydraulics with particular reference to sediment transport and deposition and erosion control
 - (vi) Hydrogeology with particular reference to seepage and groundwater solute transport processes and monitoring thereof, or
- (b) Sufficient knowledge and experience to certify that where the **suitably qualified and experienced person** has relied on advice and information provided by other **persons with relevant expertise**
- (c) The expert providing the advice and information has knowledge, competency, suitable experience and demonstrated expertise in the matters related to watercourse diversions.

Persons with relevant expertise include:

- Geomorphologist: person who has demonstrated competency and relevant experience in stream geomorphology and watercourse diversions.
- Geotechnical Expert: person who has demonstrated competency and relevant experience in geotechnical assessment of soil characteristics suitable for watercourse diversions.
- Vegetation Expert: person who has demonstrated competency and relevant experience in the identification, role and function of vegetation with watercourses and adjoining floodplains, and has demonstrated competency and relevant experience in revegetation of watercourse diversions and adjoining floodplains.
- Groundwater Expert: person who has demonstrated competency and relevant experience in groundwater systems.
- Surface Water Expert: person who has demonstrated competency and relevant experience in hydrology.
- Engineer: person who is a Registered Professional Engineer of Queensland (RPEQ) under the provisions of the *Professional Persons Act 2002* or has similar qualifications under a respected professional registration association, and has demonstrated competency and relevant experience in design and construction of watercourse diversions.

- **Soils Expert:** person who has demonstrated competency and relevant experience in soil classification including the physical, chemical and hydrologic analysis of soil.

Trivial harm means environmental harm which is not material or serious environmental harm and will not cause actual or potential loss or damage to property of an amount of, or amounts totalling more than \$5,000.

Tolerable limits means a range of parameters regarded as being sufficient to meet the objective of protecting relevant environmental values. For example, a range of settlement for a tailings capping, rather than a single value, could still meet the objective of draining the cap quickly, preventing pondage and limiting infiltration and percolation.

µS/cm means microsiemens per centimetre.

µg/L means micrograms per litre.

Void means any man-made, open excavation in the ground.

Waste as defined in section 13 of the *Environmental Protection Act 1994*.

Waste water means used water from the activity, process water or contaminated storm water.

Water is defined under Schedule 4 of the *Water Act 2000*.


Waters includes river, stream, lake, lagoon, pond, swamp, wetland, unconfined surface water, unconfined natural or artificial watercourse, bed and bank of any waters, dams, non-tidal or tidal waters (including the sea), storm water channel, storm water drain, and groundwater and any part thereof.

WaTERS means the Queensland Government's WaTERS database system.

Water quality means the chemical, physical and biological condition of water.

Appendices

Appendix 1 Authorised Disturbance Footprint



 Anglo American	
Title: Lake Lindsay Disturbance	Author: Anglo American
Date: 5/12/2024	Spatial Reference:
Drawing Version: 1	Name: GDA 1994 MGA Zone 55
Status: Final	Disclaimer
Anglo American does not accept and disclaims any and all liability or responsibility arising from any use or reliance on this drawing. This drawing is confidential and all intellectual property rights embodied or referenced in this drawing remain the property of Anglo American.	


Legend

- Mine Lease Boundaries
- EPML00739113 Disturbance Footprint
 - Surface Disturbance Authorised
 - Surface and Subsurface Disturbance Authorised




Earthstar Geographics

Appendix 2 Release Points and Monitoring Points for Lake Lindsay Mine



Appendix 3 Locations of Prescribed Environmental Matters:

Figure 3.1 Connectivity Areas and Protected Wildlife Habitat (Endangered and Vulnerable)





Title: Map	Author: Esri Australia
Date: 15/09/2023	Spatial Reference:
Drawing Version: 1	Name: AGD 1984 AMG Zone 55
Status: Draft	Disclaimer Anglo American does not accept and disclaims any and all liability or responsibility arising from any use or reliance on this drawing. This drawing is confidential and all intellectual property rights embodied or referenced in this drawing remain the property of Anglo American.

00.51KM

Scale: 1:29,823

N

- Legend
-  Connectivity (12ha)
 -  Ornamental Snake Habitat (2.8ha)
 -  Koala and Squatter Pigeon Habitat (17ha)
 -  Lake Lindsay Extension Boundary

Figure 3.2 Protected Wildlife Habitat Special Least Concern



**AngloAmerican**

Title: Echinidna Habitat		Author: Esri Australia	
Date: 9/21/2023		Spatial Reference:	
Status: Draft		Name: WGS 1984 Web Mercator	
Revision: 0.1		Disclaimer	
00.51 KM Scale: 1:30,000		Anglo American does not accept and disclaims any and all liability or responsibility arising from any use or reliance on this drawing. This drawing is confidential and all intellectual property rights embodied or referenced in this drawing remain the property of Anglo American.	

Department of Resources, Dept. of Environment and Science, Esri, HERE, Garmin, FourSquare, METU/NASA, USGS, Esri, Geoscience Australia, NASA, NGA, USGS, Maxar

- Legend**
-  Lake Lindsay - Proposed Extension
 -  Echinidna (70ha)

END OF ENVIRONMENTAL AUTHORITY